

SHORT-TERM PAVEMENT MARKING SCHEDULE

LOCATION STA TO STA	SHORT-TERM PAVEMENT MARKING			WORKZONE PAVEMENT MARKING REMOVAL
	WHITE-SOLID	WHITE-SKIP DASH	YELLOW-SOLID	
	FOOT	FOOT	FOOT	SQ FT
IL 13				
EBL				
STA 854+50.00 TO STA 858+15.00				491.9
STA 858+15.00 TO STA 859+47.26	132.0			44.0
STA 858+15.00 TO STA 859+71.50	157.0			52.3
STA 858+15.00 TO STA 859+79.65	165.0	40.0		68.3
STA 859+48.26 STOP BAR	156.0			52.0
STA 859+78.65 STOP BAR	216.0			72.0
STA 859+74.43 RUSSELL ST STOP BAR	108.0			36.0
STA 860+75.40 RUSSELL ST STOP BAR	108.0			36.0
STA 861+00.98 TO STA 861+86.66		24.0		8.0
STA 861+42.07 TO STA 871+11.22 SHOULDER		120.0		13.3
STA 861+86.66 TO STA 880+16.17		1,104.0		122.7
STA 870+00.00 TO STA 871+35.72	408.0			45.3
STA 871+97.18 BENTLEY ST STOP BAR	174.0			58.0
STA 872+49.12 TO STA 876+19.96 SHOULDER		48.0		5.3
STA 875+00.00 TO STA 876+36.03	408.0			45.3
STA 876+91.90 VICKSBURG ST STOP BAR	108.0			36.0
STA 880+16.17 TO STA 883+90.59		240.0		26.7
STA 880+33.09 HIGHLAND AVE STOP BAR	138.0			46.0
STA 882+23.56 TO STA 883+25.00	306.0			34.0
STA 883+70.35 JOHNSON STOP BAR	114.0			38.0
WBL				
STA 858+72.67 TO STA 859+48.26		16.0		5.3
STA 860+79.84 RUSSELL ST STOP BAR	108.0			36.0
STA 860+87.77 STOP BAR	288.0			96.0
STA 860+94.12 TO STA 862+76.30	182.0			60.7
STA 860+87.77 TO STA 862+76.30		40.0		13.3
STA 860+87.77 TO STA 863+12.33	225.0			75.0
STA 862+76.30 TO STA 880+15.53		1,056.0		117.3
STA 871+66.25 BENTLEY ST STOP BAR	198.0			66.0
STA 872+34.40 TO STA 873+47.85	342.0			38.0
STA 876+69.58 DUFOUR ST STOP BAR	174.0			58.0
STA 877+30.96 TO STA 880+05.09	822.0			91.3
STA 880+15.53 TO STA 883+25.00		192.0		21.3
STA 880+68.73 TO STA 881+72.78	312.0			34.7
STA 883+25.00 TO STA 886+11.76		32.0		11.7
STA 883+57.30 JOHNSON ST. STOP BAR	84.0			28.0
STA 886+60.19 IL 37 STOP BAR	108.0			36.0
RUSSEL ST.				
STA 9+20.06 STOP BAR	144.0			48.0
STA 9+20.06 TO STA 8+00.00	120.0		120.0	80.0
STA 10+62.93 TO STA 11+81.03	354.0		118.0	157.3
STA 10+69.85 STOP BAR	264.0			88.0
SUB TOTALS	6,423.0	2,912.0	238.0	
PROJECT TOTALS				2,493.0