

FUNDING:	80% FEDERAL/ 20% STATE		
LOCATION:	URBAN		
COUNTY:	WILLIAMSON		
ROUTE:	FAP 331 (IL 13)	FAP 331 (IL13/IL37 INTERSECTION)	FAP 331 (IL 13)
CONST TYPE CODE:	0003	0003	0021

CODE NUMBER	PAY ITEM DESCRIPTION	UNIT	PROJECT TOTAL QUANTITY	ROADWAY	ROADWAY	SIGNALS & LIGHTING
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	18,524	16,431	2,093	
42400800	DETECTABLE WARNINGS	SQ FT	160	150	10	
44000100	PAVEMENT REMOVAL	SQ YD	8,607	8,205	402	
44000162	HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/4"	SQ YD	13,084	13,084		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	3,085	2,699	386	
44000600	SIDEWALK REMOVAL	SQ FT	4,240	3,587	653	
44003100	MEDIAN REMOVAL	SQ FT	1,846	1,600	246	
44004250	PAVED SHOULDER REMOVAL	SQ YD	3,592	3,592		
44201007	CLASS B PATCHES, TYPE II, 13 INCH	SQ YD	114	114		
44201011	CLASS B PATCHES, TYPE III, 13 INCH	SQ YD	154	154		
44201013	CLASS B PATCHES, TYPE IV, 13 INCH	SQ YD	28	28		
44201299	DOWEL BARS 1 1/2"	EACH	368	368		
44213100	PAVEMENT FABRIC	SQ YD	99	99		
44213200	SAW CUTS	FOOT	1,006	1,006		