

NOTES

Prestressing steel shall be uncoated high strength, low relaxation 7-wire strand, Grade 270. The nominal diameter shall be 1/2" and the nominal cross-sectional area shall be 0.153 sq. in. The 1" rods in the transverse tie assembly shall be tightened to a snug fit and the threads set. Pockets on exterior faces of bridge shall be filled with grout after transverse tie assembly is in place.

Reinforcement bars shall conform to ASTM A 706, Grade 60.

Two 1/8" fabric adjusting shims of the dimensions of the exterior bearing pad shall be provided for each bearing pad location.

A minimum 2 1/2" lifting pin shall be used to engage the lifting loops during handling.


Corrosion Inhibitor, per Article 1020.05(b)(12) and 1021.06 of the Standard Specifications, shall be used in the concrete for precast prestressed concrete deck beams.

Compressive strength of prestressed concrete, f'c, shall be 6000 psi.

Compressive strength of prestressed concrete at release, f'ci, shall be 5000 psi.

BILL OF MATERIAL

Precast Prestressed Conc. Deck Bms. (17" depth)	Sq. Ft.	2473
---	---------	------



PD-1736-RD 7-1-10

FILE NAME: J:\B9029\CADD\CAD\Drawings\011-3417\0304110-27029-Sh+PPC Deck Beam.dgn	DESIGNED - NIEWINSKI	REVISIONS - AM 9/09/2011
USER NAME: amander	CHECKED - TRELLO	REVISIONS -
PLT SCALE: #0.6, 17 ft/ft / in.	DRAWN - VERENSKI	REVISIONS -
PLT DATE: #4/18/2012	CHECKED - TRELLO	REVISIONS -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**17" x 36" PPC DECK BEAM DETAILS
STRUCTURE NO. 011-3417**

SHEET NO. 4 OF 10 SHEETS

T.P. RT.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
307A	08-04118-DO-BR	CHRISTIAN	26	12
CONTRACT NO. 93507				
ILLINOIS FED. AID PROJECT: BR05-0021 (162)				

PLT DRIVER: #PLDTT#