



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

July 26, 2018

SUBJECT: FAS 212 (Joy Road)
Section 14-00103-02-DR
Mercer County
Contract No. 89741
Item 53
August 3, 2018 Letting
Addendum (A)

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised page 2 of the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bid.

Very truly yours,

Jack A. Elston, P.E.
Bureau Chief
Engineer of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger P.E.".

By: Ted B. Walschleger, P.E.
Engineer of Project Management

PRECAUTIONS FOR UTILITIES

The Contractor shall take whatever precautions which may be necessary to protect the property of the various public utilities which may be located underground or above ground, at or adjacent to the site of these improvements. If so required, the respective utility companies will make the needed adjustments of these facilities. These facilities shall be saved harmless and care shall be exercised so as not to disrupt or destroy the services provided by these utilities. The Contractor will be required to repair or replace any utility property, which has been damaged through his/her efforts. The procedure and specifications of repair will be in accordance with the regulations and/or policy of the utility.

THE CONTRACTOR SHALL CONTACT AND COORDINATE HIS/HER ACTIVITIES BY CONTACTING J.U.L.I.E. AT (800) 892-0123

REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL FOR STRUCTURES

ROCK FILL (SPECIAL)

This work shall be in accordance with the applicable portions of Section 502 of the Standard Specifications for Road and Bridge Construction and as specified herein.

A contingency of 1' depth of removal and disposal and associated rock fill has been included in the contract for all locations of CONCRETE BOX CULVERTS. The plan width of the contingency shall be the same as the width offsets of POROUS GRANULAR EMBANKMENT as presented in the "SECTION THRU BARREL" culvert plan details. The Engineer shall approve all removal and disposal requests towards these contingency pay items prior to any additional excavation by the Contractor.

The material properties of any approved rock fill shall meet or exceed the standards of POROUS GRANULAR EMBANKMENT to be used in the project.

This work shall be paid for at the contract unit price per CUBIC YARD for REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL FOR STRUCTURES and ROCK FILL (SPECIAL) respectively.

CONCRETE BOX CULVERTS

This work shall be in accordance with the applicable portions of Section 540 of the Standard Specifications for Road and Bridge Construction and as specified herein.

The Contractor shall remove the existing box culvert at Station 647+23 per Art 501.04. This work will not be measured separately but shall be considered included in the contract unit price for CONCRETE BOX CULVERTS.

For the proposed culvert at Station 647+23, the Contractor shall submit for approval and use a high-early-strength mix for all portions of concrete to achieve the road closure requirements set forth in the provision "WORKING DAYS."

This work shall be paid for at the contract unit price per CUBIC YARD for CONCRETE BOX CULVERTS.