

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1382	0304 RS-3	COOK	21	3

D91-345-98

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		100% STATE URBAN 1000	50% STATE 50% VILLAGE URBAN Y025	100% VILLAGE URBAN Y025			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	5.3	4.8	0.5				
40600300	AGGREGATE (PRIME COAT)	TON	27	24	3				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	4	3.6	0.4				
40600895	CONSTRUCTING TEST STRIP	EACH	2	2					
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	196	196					
40601000	BITUMINOUS REPLACEMENT OVER PATCHES	TON	78	55		23			
42001300	PROTECTIVE COAT	SQ YD	38	27		11			
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	250	250					
42400800	DETECTABLE WARNINGS	SQ FT	120	120					
44000006	BITUMINOUS SURFACE REMOVAL 1 1/2"	SQ YD	6000	6000					
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	2929	1573	1356				
44000110	BITUMINOUS REMOVAL OVER PATCHES 2 1/2"	SQ YD	740	525		215			
44000600	SIDEWALK REMOVAL	SQ FT	250	250					
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	220	156		64			
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	350	299		51			
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	180	154		26			
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	210	179		31			
55039700	STORM SEWERS TO BE CLEANED	FOOT	880	880					
60250200	CATCH BASINS TO BE ADJUSTED	EACH	5	5					
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	3	3					
60264130	INLETS TO BE RECONSTRUCTED WITH NEW TYPE 23 FRAME AND GRATE	EACH	3	2		1			
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	23	23					
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	8	7		1			
60404940	FRAMES AND GRATES, TYPE 23	EACH	9	7		2			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5	5					
67100100	MOBILIZATION	L SUM	1	1					
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1					
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	872	872					

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		100% STATE URBAN 1000	50% STATE 50% VILLAGE URBAN Y025	100% VILLAGE URBAN Y025			
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	72.8	72.8					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	1342	1342					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	511	511					
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	248	248					
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	167	167					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	233	233					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	291	291					
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	72.8	72.8					
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1342	1342					
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	511	511					
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	248	248					
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	167	167					
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	233	233					
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	55	55					
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	686	686					
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4					
X0323094	TYPE 1 FRAME, OPEN LID	EACH	2	2					
X0323095	TYPE 1 FRAME, CLOSED LID	EACH	2	2					
X0656100	DRIVEWAY PAVEMENT REMOVAL AND REPLACEMENT	SQ YD	70	70					
X4066424	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N50	TON	1124	1010	114				
X4067100	POLYMERIZED LEVELING BINDER (MACHINE METHOD), SUPERPAVE, IL-4.75, N50	TON	562	505	57				
X4409410	BITUMINOUS SURFACE REMOVAL 2 1/4"	SQ YD	4460	4460					
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	15	15					

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES  
FULLERTON AVENUE

\*SPECIALTY ITEMS

5/5/2006 10:51:14 AM