F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94	*	COOK	312	9
STA.		TO STA.		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

60A62 * (1919.15, 2021-922 PT1 & PT2) R-1

SUMMARY OF QUANTITIES

				90% FEDERAL / 10% STATE									
				URBAN ROADWAY	RETAINING WALL		BRIDGE		SIGNING	SAFETY	LIGHTING	SURVEILLANCE	CDOT LIGHTING
					016-W923	016-W931	STR NO 016-0142	STR NO 016-1148					
CODE NO.	ITEM	UNIT	QUANTITY	J000	Y007	Y007	~~SFTY-2A~~	~~SFTY-2A~~	Y002-1C	SFTY-3N	Y030-1E	Y032-1F	~~Y030-1E~~
60109582	PIPE UNDERDRAINS FOR STRUCTURES 6"	FOOT	8			8							
60200105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	2	2									
60200205	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1									
60201310	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 20 FRAME AND GRATE	EACH	67	67									
60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	21	21									
60205010	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 20 FRAME AND GRATE	EACH	1	1									
60208210	CATCH BASINS, TYPE C, TYPE 20 FRAME AND GRATE	EACH	6	6									
60208240	CATCH BASINS, TYPE C, TYPE 24 FRAME AND GRATE	EACH	1	1									
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	10	10									
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3	3									
60250400	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	1	1									
60250500	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	2	2									
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	2	2									
60500040	REMOVING MANHOLES	EACH	14	14									
60500050	REMOVING CATCH BASINS	EACH	73	73									
60500060	REMOVING INLETS	EACH	52	52									
60608521	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2.24	FOOT	1,035	1,035									
60618324	CONCRETE MEDIAN SURFACE, 6 INCH (SPECIAL)	SQ FT	8,295	8,295									
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	787.5	787.5									
* 63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	1	1									
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	3	3									
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT)	EACH	2	2									
63200310	GUARDRAIL REMOVAL	FOOT	1,773	1,773									
63700805	CONCRETE BARRIER TRANSITION	FOOT	798	798									
64200105	SHOULDER RUMBLE STRIP	FOOT	33,399	33,399									
66400305	CHAIN LINK FENCE, 6'	FOOT	296	296									
67100100	MOBILIZATION	L SUM	1	1									
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1									
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	5,580	5,580									
70300510	PAVEMENT MARKING TAPE, TYPE III - LETTERS AND SYMBOLS	SQ FT	180	180									

* DENOTES SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 90/94 (DAN RYAN EXPRESSWAY)
63RD STREET TO GARFIELD BLVD (NB LOCAL LANES)

SUMMARY OF QUANTITIES

SCALE: NONE DRAWN BY: NJH
DATE: June 9, 2006 CHECKED BY: RMG

CTE | AECOM

SQQ-3

6/6/2006 9:38:40 AM