

SEWER REMOVAL ITEMS cont.

SHEET NUMBER	FROM		TO		STORM SEWER REMOVAL 10" (FT)	STORM SEWER REMOVAL 12" (FT)	STORM SEWER REMOVAL 15" (FT)	STORM SEWER REMOVAL 21" (FT)	STORM SEWER REMOVAL 36" (FT)	PIPE UNDERDRAIN REMOVAL (FT)	WATERMAIN REMOVAL (FT)	PLUG AND ABANDON EXISTING PIPE (CU YD)	TRENCH BACKFILL (CU YD)
	STATION	OFFSET	STATION	OFFSET									
DU-14	4460+51	5' LT	4460+60	8' LT								0.2	0.0
DU-14	4460+50	51' RT	4461+12	54' RT		62							22.8
DU-14	4461+14	64' RT	4461+13	55' RT	9								3.1
DU-14	4461+14	54' RT	4461+84	56' RT		70							25.7
DU-14	4461+16	39' RT	4461+08	0' RT	40								13.7
DU-14	4461+08	0' RT	4461+18	2' LT	10								3.4
DU-14	4461+08	0' RT	4461+09	4' LT	5								1.7
DU-14	4461+09	4' LT	4461+09	8' LT								0.1	0.0
DU-14	4461+97	70' RT	4461+96	7' LT						77			0.0
DU-14	4463+02	38' RT	4463+13	46' RT					14				0.0
DU-14	4463+01	36' RT	4463+01	5' LT		41							11.8
DU-14	4463+01	0' RT	4463+10	1' LT	9								2.1
DU-15	4465+44	33' RT	4465+51	38' RT	9								3.1
DU-15	4465+44	32' RT	4465+56	1' RT		34							12.5
DU-15	4465+57	0' RT	4465+64	1' LT	8								2.7
DU-15	4465+56	0' RT	4465+51	5' LT		7							2.6
DU-15	4465+51	5' LT	4465+47	9' LT								0.2	0.0
DU-15	4468+84	47' RT	4468+84	38' RT					9				0.0
DU-15	4468+84	37' RT	4468+96	28' RT		15							3.3
DU-15	4468+97	27' RT	4468+96	1' RT		26							7.3
DU-15	4468+97	1' RT	4469+05	1' LT	8								2.7
DU-15	4468+96	0' RT	4468+97	5' LT		5							0.0
DU-16	4471+08	36' RT	4471+08	28' RT		8							0.0
DU-16	4471+08	27' RT	4471+07	1' RT		26							0.0
DU-16	4471+08	0' RT	4471+16	1' LT	8								2.7
DU-16	4471+07	0' RT	4471+07	5' LT		5							0.0
DU-16	4472+62	37' RT	4473+11	28' RT	50								17.1
DU-16	4473+12	27' RT	4473+15	1' RT	27								9.2
DU-16	4473+16	0' RT	4473+23	1' LT	8								2.7
DU-16	4473+15	0' RT	4473+16	5' LT		5							0.0
DU-16	4473+70	28' RT	4473+72	36' RT	8								2.7
DU-16	4473+72	37' RT	4473+76	1' RT	37								12.7
DU-16	4473+68	1' LT	4473+75	1' RT	8								2.7
DU-16	4473+76	0' RT	4473+78	5' LT		6							2.2
DU-16	4473+78	5' LT	4473+78	7' LT								0.1	0.0
DU-16	4473+79	7' LT	4473+83	5' LT								0.1	0.0
DU-16	4473+83	5' LT	4474+38	27' RT	64								21.9
DU-16	4474+01	41' RT	4474+02	8' LT	49								16.8
DU-16	4474+31	1' LT	4474+38	1' RT	8								2.7
DU-16	4474+39	2' RT	4474+39	26' RT	24								8.2
TOTALS					1,802	1,487	504	8	20	1,017	244	7.8	1168.6

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94	*	COOK	312	81
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS	FED. AID PROJECT	
60A62		• (1919.15, 2021-922 PT1 & PT2) R-1		

PLAN 4468+84 NB CHANGES 18 & 19 OFF CENTER DRAINAGE AND UTILITY PLAN 180151800032.DWG

CTE | AECOM

REVISIONS	
NAME	DATE

DS-3

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 F.A.I. 90/94 (DAN RYAN EXPRESSWAY)  
 63RD STREET TO GARFIELD BLVD (NB LOCAL LANES)

**DRAINAGE SCHEDULES**

SCALE: NONE  
 DATE: June 9, 2006

DRAWN BY: NJH  
 CHECKED BY: RMG

6/5/2006 9:14 AM