

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	2005-062 I	WILL	72	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

**SUMMARY OF QUANTITIES**

URBAN  
901.FED.  
101.STATE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	Y002-1C
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	61	61
28000300	TEMPORARY DITCH CHECKS	EACH	7	7
28000500	INLET AND PIPE PROTECTION	EACH	2	2
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	823	823
* 50200400	ROCK EXCAVATION FOR STRUCTURES	CU YD	31.5	31.5
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	1825	1825
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	4	4
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	4	4
* 63302000	REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	5	5
67100100	MOBILIZATION	L SUM	1	1
72000200	SIGN PANEL - TYPE 2	SQ FT	20	20
72000300	SIGN PANEL - TYPE 3	SQ FT	1226	1226
72400320	REMOVE SIGN PANEL - TYPE 2	SQ FT	20	20
72400330	REMOVE SIGN PANEL - TYPE 3	SQ FT	1031	1031
72400730	RELOCATE SIGN PANEL - TYPE 3	SQ FT	1288	1288
73300100	OVERHEAD SIGN STRUCTURE - SPAN, TYPE I-A (4'-0" X 4'-6")	FOOT	414	414
73300200	OVERHEAD SIGN STRUCTURE - SPAN, TYPE II-A (4'-6" X 5'-3")	FOOT	104	104
73302210	OVERHEAD SIGN STRUCTURE - CANTILEVER, TYPE III-C-A (36" X 7'-0")	FOOT	40	40
73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	192.9	192.9
73600100	REMOVE OVERHEAD SIGN STRUCTURE - SPAN	EACH	6	6
73700300	REMOVE CONCRETE FOUNDATION - OVERHEAD	EACH	12	12
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	21	21
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4
* X6330103	REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL, TANGENT	EACH	3	3
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1
X7330105	OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	273.75	273.75
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1
<del>Z0076600</del>	<del>TRAINERS</del>	<del>HOUR</del>		
X0325336	TOPSOIL FURNISH AND PLACE, VARIABLE DEPTH, SPECIAL	SQ YD	1878	1878

**EARTHWORK SCHEDULE**

ITEM	UNIT	QUANTITY AT SIGN STRUCTURES							TOTAL QUANTITY
		189+70.00	229+76.00	248+22.00	256+26.00	277+45.00	333+75.00	354+55.00	
REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	14.7	6.5	10.6	13.3	0.9	8.1	7.1	61.2
EARTH EXCAVATION (FOR INFORMATION ONLY) **	CU YD	19.7	9.8	82.8	16.5	3.1	2.5	10.4	144.8
TOPSOIL (FOR INFORMATION ONLY)	CU YD	42.4	9.6	42.7	14.6	0.0	13.7	12.5	135.4

\*\*EARTH EXCAVATION REQUIRED FOR THE CONSTRUCTION OF THE PROPOSED AGGREGATE SHOULDERS IS INCLUDED IN THE CONTRACT UNIT PRICE FOR AGGREGATE SHOULDERS, TYPE B 6".

\* SPECIALTY ITEMS

PLT DATE = #DATE#  
FILE NAME = #FILE#  
PLT SCALE = #SCALE#  
USER NAME = #USER#  
S:\DOCUMENT\02361561\CIVIL\08A\3007\A011.SHT  
GARCIAZ

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
FAI ROUTE 55 (I-80 TO U.S. 30)  
SIGNING

**SUMMARY OF QUANTITIES**

SCALE: N.T.S. DRAWN BY AG  
DATE 05/19/06 CHECKED BY DDH

**TENG**  
TENG & ASSOCIATES, INC.  
ENGINEERS/ARCHITECTS/PLANNERS  
CHICAGO, ILLINOIS