

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	2005-062 I	WILL	72	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SCHEDULE OF QUANTITIES - SIGNING

CODE NO.	ITEM	UNIT	TOTAL QUANTITY
72000200	SIGN PANEL - TYPE 2	SQ FT	20
72000300	SIGN PANEL - TYPE 3	SQ FT	1226
73400320	REMOVE SIGN PANEL - TYPE 2	SQ FT	20
72400330	REMOVE SIGN PANEL - TYPE 3	SQ FT	1031
72400730	RELOCATE SIGN PANEL - TYPE 3	SQ FT	1288
73300100	OVERHEAD SIGN STRUCTURE - SPAN, TYPE I-A (4'-0" X 4'-6")	FOOT	414
73300200	OVERHEAD SIGN STRUCTURE - SPAN, TYPE II-A (4'-6" X 5'-3")	FOOT	104
73300210	OVERHEAD SIGN STRUCTURE - CANTILEVER, TYPE III-C-A (36" X 7'-0")	FOOT	40
73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	192.9
73600100	REMOVE OVERHEAD SIGN STRUCTURE - SPAN	EACH	6
73700300	REMOVE CONCRETE FOUNDATION - OVERHEAD	EACH	12
7330100	OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	273.75

SIGN PANEL - TYPE 3 AND RELATED STRUCTURES - INSTALLATION AND REMOVAL

PAY ITEM	1S0991055R249.90	1S0991055L250.67	1S0991055R251.02	1S0991055L251.17	1C0991055R251.56	1S0991055R252.64	1S0991055L253.03	TOTAL QUANTITY	UNIT
	189+70	229+76	248+22	256+26	277+45	333+75	354+55		
SIGN PANEL - TYPE 2	12'-6" x 12'-6"	12'-6" x 12'-6"	13'-0" x 14'-6"	12'-6" x 12'-6"	12'-6" x 12'-6"	11'-6" x 12'-6"	14'-6" x 12'-6"	20	SQ FT
SIGN PANEL - TYPE 3	12'-6" x 12'-6"	12'-6" x 12'-6"	16'-0" x 14'-6"	12'-6" x 12'-6"	12'-6" x 12'-6"	16'-0" x 12'-6"	16'-0" x 12'-6"	188.5	SQ FT
REMOVE SIGN PANEL - TYPE 2	14'-0" x 12'-6"	14'-0" x 12'-6"						20	SQ FT
REMOVE SIGN PANEL - TYPE 3								1031	SQ FT
RELOCATE SIGN PANEL - TYPE 3	487.5	487.5		312.5	325	325	381.25	1288	SQ FT
OVERHEAD SIGN STRUCTURE - SPAN, TYPE I-A (4'-0" X 4'-6")		77	75	82		91	89	414	FOOT
OVERHEAD SIGN STRUCTURE - SPAN, TYPE II-A (4'-6" X 5'-3")	104							104	FOOT
OVERHEAD SIGN STRUCTURE - CANTILEVER, TYPE III-C-A (36" X 7'-0")					40			40	FOOT
DRILLED SHAFT CONCRETE FOUNDATIONS	33.4	29.3	31.6	30.6	12.6	25.7	29.7	192.9	CU YD
REMOVE OVERHEAD SIGN STRUCTURE - SPAN	1	1		1	1	1	1	6	EACH
REMOVE CONCRETE FOUNDATION - OVERHEAD	2	2		2	2	2	2	12	EACH
OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	46.08	46.83	40.83	37.17	25.42	38.75	38.67	273.75	FOOT

FILE DATE = 05/19/06
 FILE NAME = 051906.DWG
 PLOT SCALE = 1/8"=1'-0"
 USER NAME = JGARCIA

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 I-55 ROUTE 55 (I-80 TO U.S. 30)
 SIGNING

SCHEDULE OF QUANTITIES

SCALE: N.T.S. DRAWN BY: AG
 DATE: 05/19/06 CHECKED BY: DDH

TENG TENG & ASSOCIATES, INC.
 ENGINEERS/ARCHITECTS/PLANNERS
 CHICAGO, ILLINOIS

Rev.