

F.A.U. SHEETS	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2710	(1213&3219) RS-7	COOK	22	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

60B32

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	100% STATE 1000				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	3.4	3.4				
40600300	AGGREGATE (PRIME COAT)	TON	17	17				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	1	1				
40600895	CONSTRUCTING TEST STRIP	EACH	1	1				
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	48	48				
40601000	BITUMINOUS REPLACEMENT OVER PATCHES	TON	541	541				
44000006	BITUMINOUS SURFACE REMOVAL 1 1/2"	SQ YD	8456	8456				
44000115	BITUMINOUS REMOVAL OVER PATCHES 3 3/4"	SQ YD	3221	3221				
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	1288	1288				
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	966	966				
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	966	966				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	1	1				
67100100	MOBILIZATION	L SUM	1	1				
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1				
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1				
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	6	6				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	3582	3582				
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	165	165				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	10000	10000				
* 70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	160	160				
* 70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	104	104				
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	244	244				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	10000	10000				
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	160	160				
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	162	162				

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	100% STATE 1000				
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	104	104				
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	500	500				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	500	500				
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	120	120				
X0322467	TEMPORARY INFORMATION SIGNING FOR LANE CLOSURE	SQ FT	96	96				
X4066426	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	710	710				

6/6/2006 08:00:00 AM C:\PLOT\1001322083\60B32.DWG

* SPECIALTY ITEMS Rev

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION ILL. ROUTE 38 (STATE STREET) FROM ILL. 25 TO EAST SIDE DRIVE (7th ST.) SUMMARY OF QUANTITIES
NAME	DATE	
		PLOT DATE: 6/6/2006