

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
326	E-8-4-B	KANE	62	4
FED. ROAD DIST. NO. 1		ILLINOIS FED. AID PROJECT		

CONTRACT NO. 62531
 ISTHA CONTRACT RR-02-5129
 ISTHA BRIDGE NO. 1101

CODE #	PAY ITEM	UNIT	URBAN TOTAL QUANTITY	100% STATE		100% ISHTA	
				CONSTRUCTION CODE			
				J000-2A	X281-2A	SN. # 045-0082	
		ROADWAY	IDOT	ISTHA			
20200100	EARTH EXCAVATION	CU YD	550	550			
20201006	GRADING AND SHAPING SHOULDERS	UNIT	22	22			
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	235	235			
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	2,075	2,075			
25000210	SEEDING, CLASS 2A	ACRE	0.5	0.5			
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	39	39			
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	39	39			
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	39	39			
25100630	EROSION CONTROL BLANKET	SQ YD	2,075	2,075			
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	43	43			
28000400	PERIMETER EROSION BARRIER	FOOT	2,610	2,610			
28100107	STONE RIPRAP, CLASS A4	SQ YD	915			915	
28200200	FILTER FABRIC	SQ YD	915			915	
31101100	SUB-BASE GRANULAR MATERIAL, TYPE B	CU YD	62	62			
31101400	SUB-BASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	2,760	2,760			
42001300	PROTECTIVE COAT	SQ YD	3,168	617	2,551		
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	536	536			
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	73	73			
44000100	PAVEMENT REMOVAL	SQ YD	73	73			
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	147	147			
44000700	APPROACH SLAB REMOVAL	SQ YD	485	485			
44003100	MEDIAN REMOVAL	SQ FT	815	815			
44004250	PAVED SHOULDER REMOVAL	SQ YD	2,448	2,448			
48101200	AGGREGATE SHOULDERS, TYPE B	TON	30	30			
48202600	BITUMINOUS SHOULDERS SUPERPAVE B"	SQ YD	34	34			
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1		1		
50102400	CONCRETE REMOVAL	CU YD	18.6			18.6	
50104650	SLOPE WALL REMOVAL	SQ YD	2			2	
50300150	NEOPRENE EXPANSION JOINT 2"	FOOT	190		190		
50300225	CONCRETE STRUCTURES	CU YD	34.5			34.5	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	734.9		734.9		
50300260	BRIDGE DECK GROOVING	SQ YD	1,800		1,800		
50300310	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	24			24	
50401005	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE I-BEAMS, 48 IN.	FOOT	1,984			1,984	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	165,740		163,330	2,410	
51100100	SLOPE WALL 4 INCH	SQ YD	2			2	
51500100	NAME PLATES	EACH	1		1		
58700200	BRIDGE SEAT SEALER	SQ FT	430			430	
59000100	EPOXY CRACK SEALING	FOOT	263			263	
60607400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-9.24	FOOT	24	24			
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	808	808			
* 63000000	STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	350	350			
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4			
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	2	2			

* SPECIALTY ITEM

CODE #	PAY ITEM	UNIT	URBAN TOTAL QUANTITY	100% STATE		100% ISHTA	
				CONSTRUCTION CODE			
				J000-2A	X281-2A	SN. # 045-0082	
		ROADWAY	IDOT	ISTHA			
63200310	GUARDRAIL REMOVAL	FOOT	235	235			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8	8			
67100100	MOBILIZATION	L SUM	1	0.5	0.5		
70100320	TRAFFIC CONTROL AND PROTECTION, STANDARD 701422	L SUM	1	1			
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1			
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	20	20			
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	364	364			
70300510	PAVEMENT MARKING TAPE, TYPE III - LETTERS AND SYMBOLS	SQ FT	218	218			
70300540	PAVEMENT MARKING TAPE, TYPE III 6"	FOOT	863	863			
70300560	PAVEMENT MARKING TAPE, TYPE III 12"	FOOT	219	219			
70400100	TEMPORARY CONCRETE BARRIER	FOOT	540	540			
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	480	480			
* 78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SQ FT	73	73			
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	9,057	9,057			
* 78008230	POLYUREA PAVEMENT MARKING TYPE I - 6"	FOOT	305	305			
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	2	2			
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	12	12			
* 78200410	GUARDRAIL MARKERS - TYPE A	EACH	8	8			
* 78200520	BARRIER WALL MARKERS, TYPE B	EACH	6	6			
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2			
78300100	PAVEMENT MARKING REMOVAL	SQ FT	2,717	2,717			
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4			
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5")	SQ FT	168			168	
X0323082	DRAINAGE SCUPPERS, DS-33	EACH	2		2		
X0751105	REMOVAL OF EXISTING CONCRETE DECK NO. 1	EACH	1		1		
X0751205	REMOVAL OF EXISTING CONCRETE DECK NO. 2	EACH	1		1		
X3550405	BITUMINOUS BASE COURSE SUPERPAVE 7 1/4"	SQ YD	2,765	2,765			
X4066424	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE MIX "D", N50	TON	271	271			
X6050700	REMOVE INLET BOX	EACH	2	2			
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1			
X7030100	WET TEMPORARY PAVEMENT MARKING TAPE TYPE III	FOOT	23,216	23,216			
Z0002600	BAR SPLICERS	EACH	807		803	4	
Z0018800	DRAINAGE SYSTEM	L SUM	1			1	
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2			
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2			
Z0047300	PROTECTIVE SHIELD	SQ YD	3,138			3,138	
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1			
Z0076600	TRAINERS	HOOR					
X0325490	FURNISH AND INSTALL ACCESS DOOR	EACH	2			2	

* SPECIALTY ITEM



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 F.A.P. ROUTE 326 (IL 47)

SUMMARY OF QUANTITIES

VERT. SCALE: HORIZ. DATE: MARCH 21, 2006

DRAWN BY: NEC
 CHECKED BY: SPF

5/8/2006 9:50:34 AM K:\1182522\CAD\Des\Gm\182522_SumQty.dgn