

PAVEMENT SCHEDULE									
LOCATION	SUB-BASE GRANULAR MATERIAL TYPE B (CU YD)	SUB-BASE GRANULAR MATERIAL TYPE B 6" (SQ YD)	PROTECTIVE COAT (SQ YD)	BRIDGE APPROACH PAVEMENT (SPECIAL) (SQ YD)	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC) (SQ YD)	BITUMINOUS SHOULDERS SUPERPAVE 8" (SQ YD)	BITUMINOUS BASE COURSE SUPERPAVE, 7 1/4" (SQ YD)	CONCRETE MEDIAN SURFACE, 4" (SQ FT)	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N50 (TON)
NORTHBOUND									
STA. 52+24.85 TO 53+55.00		7	141	125	16	8.5	7		1
STA. 53+55.00 TO 55+81.92		1634	186	161	25	8.5	306		30
STA. 58+20.92 TO 61+58.00							1330		130
STA. 61+58.00 TO 72+46.80									
MEDIAN									
STA. 55+45.92 TO 55+81.92	42							606	
STA. 58+20.92 TO 58+56.92	20							202	
SOUTHBOUND									
STA. 49+25.20 TO 52+44.10		316					315		31
STA. 53+55.00 TO 55+81.92		7	141	125	16	8.5	7		1
STA. 58+20.92 TO 61+58.00		478	141	125	16	8.5	480		47
STA. 61+58.00 TO 61+92.63									
STA. 62+99.78 TO 65+85.87		318					320		31
TOTAL	62	2760	609	536	73	34.0	2765	808	271

CURB & GUTTER / MEDIAN			
LOCATION	COMBINATION CONCRETE CURB AND GUTTER TYPE B-9.24 (FOOT)	CONCRETE MEDIAN SURFACE, 4 INCH (SQ FT)	PROTECTIVE COAT (SQ YD)
MEDIAN			
RT. STA. 55+43.10 TO 55+49.10	6		2
RT. STA. 58+52.12 TO 58+58.12	6		2
STA. 55+45.92 TO 55+81.92		606	
LT. STA. 55+48.74 TO 55+54.74	6		2
LT. STA. 58+53.74 TO 58+59.74	6		2
STA. 58+20.92 TO 58+56.92		201.5	
TOTAL	24	808	8

PAVEMENT MARKING SCHEDULE											
LOCATION	WET TEMPORARY PAVEMENT MARKING TAPE, TYPE III (FOOT)	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS (SQ FT)	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"(FOOT)	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"(FOOT)	RAISED REFLECTIVE PAVEMENT MARKER (EACH)	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE) (EACH)	PAVEMENT MARKING TAPE, TYPE III - LETTERS & SYMBOLS (SQ FT)	PAVEMENT MARKING TAPE, TYPE III 6" (FOOT)	PAVEMENT MARKING TAPE, TYPE III 12" (FOOT)	GUARDRAIL MARKERS - TYPE A (EACH)	BARRIER WALL MARKERS - TYPE B (EACH)
STAGE I (NORTHBOUND)											
STA. 46+22.85 TO 67+58.18	4,838										
STAGE I (MEDIAN & TURN LANE)											
STA. 47+23.28 TO 61+90.41	2,024						72.6	284	38		
STA. 63+82.74 TO 71+00.00	1,685								122		
STAGE I (SOUTHBOUND)											
STA. 49+39.00 TO 52+28.43	294										
STA. 53+54.92 TO 61+94.86	642										
STA. 62+98.37 TO 65+85.73	288										
STAGE II (NORTHBOUND)											
STA. 51+20.44 TO 72+46.66	5,254										
STAGE II (MEDIAN & TURN LANE)											
STA. 45+00.00 TO 53+55.00							72.6	232	29		
STA. 53+55.00 TO 61+58.00	1,135								30		
STA. 61+58.00 TO 72+73.68	1,516										
STAGE II (SOUTHBOUND)											
STA. 49+48.97 TO 53+55.00	527										
STA. 53+55.00 TO 61+83.81	879										
STA. 61+83.81 TO 67+77.15	1,173										
NORTHBOUND											
STA. 44+96.86 TO 72+73.67				1,916							
STA. 49+47.77 TO 61+58.00				340						4	3
STA. 53+55.00 TO 61+58.00					2	6					
CENTERLINE, MEDIAN & TURN LANE											
STA. 44+99.78 TO 53+55.00	444			1,552							
STA. 53+55.00 TO 61+58.00	1,622		73	1,587			72.6	347			
STA. 61+58.00 TO 72+73.67	895			2,182							
SOUTHBOUND											
STA. 44+99.70 TO 47+99.35				326							
STA. 49+25.15 TO 52+45.72				865						4	3
STA. 53+55.00 TO 61+90.41				289		6					
STA. 63+53.62 TO 72+73.67											
TOTAL	23,216		73	9,057		12	218	863	219	8	6

REMOVAL SCHEDULE								
LOCATION	PAVEMENT REMOVAL (SQ YD)	COMBINATION CURB & GUTTER REMOVAL (FOOT)	APPROACH SLAB REMOVAL (SQ YD)	MEDIAN REMOVAL (SQ FT)	PAVED SHOULDER REMOVAL (SQ YD)	GUARDRAIL REMOVAL (FOOT)	PAVEMENT MARKING REMOVAL (SQ FT)	INLET BOX REMOVAL (EACH)
NORTHBOUND								
STA. 51+82.38 TO 55+81.92								
STA. 53+55.00 TO 55+81.92	16		113		8	25	60	1
STA. 58+20.92 TO 61+58.00	25		148		1,432	89	476	
STA. 61+58.00 TO 72+46.80								
MEDIAN								
STA. 55+45.92 TO 55+81.92		72		608			687	
STA. 58+20.92 TO 58+56.92		75		207			1,076	
SOUTHBOUND								
STA. 49+25.20 TO 52+44.10					299		110	
STA. 53+55.00 TO 55+81.92	16		112		8	25		1
STA. 58+20.92 TO 61+58.00	16		112		382	96	212	
STA. 61+58.00 TO 61+92.63								
STA. 62+99.78 TO 65+85.87					319		96	
TOTAL	73	147	485	815	2,448	235	2,717	2

EARTHWORK SCHEDULE						
LOCATION	EARTH EXCAVATION (CU YD)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (CU YD)	EMBANKMENT (CU YD)	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (CU YD)	EARTHWORK BALANCE (+) WASTE (-) SHORTAGE (CU YD)	FURNISHED EXCAVATION (CU YD)
STA. 50+00.00 TO STA. 55+81.92	130	25	8	98	(+) 90	0
STA. 58+20.92 TO STA. 71+00.00	420	210	33	315	(+) 282	0

**rjngroup**  
 Excellence through Ownership  
 200 West Front Street  
 Wheaton, IL 60187

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 F.A.P. ROUTE 326 (IL 47)  
**SCHEDULE OF QUANTITIES**  
 SCALE: VERT. \_\_\_\_\_  
 HORIZ. \_\_\_\_\_  
 DATE: MARCH 21, 2006  
 DRAWN BY: NEC  
 CHECKED BY: SPF

5/8/2006 9:54:24 AM K:\102522\CAD\Design\102522\_Sched01.rvt.dgn