

F.A.I.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94/90	2003-029	COOK	344	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

62581

11/17/2006 10:39:07 AM

CODE NO.	ITEM DESCRIPTION	UNIT	URBAN 100% STATE			
			TOTAL QUANTITIES	ROADWAY J000-2A	BRIDGE X971-2A	SIGNING Y002-1C
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	875	875		
31101800	SUB-BASE GRANULAR MATERIAL, TYPE B 2 1/2"	SQ YD	875	875		
44004250	PAVED SHOULDER REMOVAL	SQ YD	779	779		
50102400	CONCRETE REMOVAL	CU YD	1096	1096		
50300255	CONCRETE SUPERSTRUCTURE	CU YD	1225.1	1225.1		
50300260	BRIDGE DECK GROOVING	SQ YD	101,406	101,406		
50300300	PROTECTIVE COAT	SQ YD	3114	3114		
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1	1		
50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	5	5		
50501110	STRUCTURAL STEEL REMOVAL	POUND	39,020	39,020		
50501130	STRUCTURAL STEEL REPAIR	POUND	3,310	3,310		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	171,670	171,670		
60250400	CATCH BASIN TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	1	1		
60255410	CATCH BASIN TO BE CLEANED	EACH	172	172		
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSE LID	EACH	4	4		
60260300	INLETS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	1	1		
60261510	INLETS TO BE ADJUSTED WITH NEW TYPE 20 FRAME AND GRATE	EACH	6	6		
60404910	FRAMES AND GRATES, TYPE 20	EACH	8	8		
63801200	MODULAR GLARE SCREEN SYSTEM	FOOT	9,974	9,974		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	10	10		
66400530	CHAIN LINK FENCE, 4' (BRIDGE)	FOOT	300	300		
67000600	ENGINEER'S FIELD LABORATORY	CAL MO	10	10		
67100100	MOBILIZATION	L SUM	1	1		
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	29,041	29,041		

S00-01

BOWMAN, BARRETT & ASSOCIATES INC.
CONSULTING ENGINEERS
Chicago, Illinois
312.228.0100
www.bbainc.com

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 94/90 (DAN RYAN EXPRESSWAY)
SB DAN RYAN ELEVATED BRIDGE
REPAIR FROM 15TH TO 28TH STREETS
SUMMARY OF QUANTITIES

SCALE: = NTS
DATE: 4/14/2006

DRAWN BY: RA
CHECKED BY: RS

Rev.

11/17/2006 10:39:07 AM