



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

July 18, 2006

SUBJECT: FAP Route 595
Project F-0595(029)
Section 1-3-LS
Rock Island County
Contract No. 64B01
Item No. 91, August 4, 2006 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised sheet 3 of the Fold up Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Michael L. Hine
Engineer of Design
and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger P.E.".

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: Gregg Mounts, Region 2, District 2;; Roger Driskell
Estimates; Design & Environment File

RS/cab

GENERAL NOTES

Fertilizer shall be applied to all disturbed areas and incorporated into the seedbed prior to seeding at the rate specified in Sections 250 and 252 of the Standard Specifications.

Planting of the pecan seedlings shall conform to Section 253 of the Standard Specification book and in addition will include the installation of one steel post per seedling for support. The post will be included in the contract unit price for pecan seedlings.

The planting of oak trees on this project shall only be planted during the spring of 2007. The contractor shall have the option of planting all other trees on this project during the fall of 2006 or in conjunction with the spring planting in 2007.

The Contractor shall be responsible for protecting utility property during construction operations as outlined in Article 107.31 of the Standard Specifications. A minimum of 48 hours advance notice is required for non-emergency work. The JULIE number is 800-892-0123. The following listed utilities located within the project limits or immediately adjacent to the project construction limits are members of JULIE:

Geneseo Telephone Co.
MidAmerican Energy Co.

SBC/Ameritech Telephone Co.

Although SEEDING CLASS 7 (SPECIAL) quantities include the entire project area, only the areas disturbed during tree planting shall be reseeded and measured for payment as SEEDING CLASS 7 (SPECIAL).



The completion dates for this contract will be dependent on tree dormancy, air temperature and other elements as indicated in Section 253 of the Standard Specifications. No working days shall be charged prior to May 1, 2007. Fifteen (15) working days have been provided for any work that is required after May 1, 2007.

 REVISED 7/17/06