

GENERAL NOTES

THE THICKNESS OF BITUMINOUS MIXTURES SHOWN ON THE PLANS IS THE NOMINAL THICKNESS. DEVIATIONS FROM THE NOMINAL THICKNESS WILL BE PERMITTED WHEN SUCH DEVIATIONS OCCUR DUE TO IRREGULARITIES IN THE EXISTING SURFACE OR BASE ON WHICH THE BITUMINOUS MIXTURE IS PLACED.

THE BITUMINOUS SURFACE OF ALL MAILBOX TURNOUTS, PRIVATE ENTRANCES, COMMERCIAL ENTRANCES, AND SIDE ROADS SHALL BE MADE NEATLY, IN A WORKMANLIKE MANNER, AND SHALL ACCURATELY CONFORM TO THE SHAPES AND DIMENSIONS SHOWN ON THE PLAN DETAILS. IF REQUIRED BY THE ENGINEER, THE CONTRACTOR SHALL BE REQUIRED TO SAW CUT THE BITUMINOUS SURFACE TO CONFORM TO THE SHAPES AND DIMENSIONS SHOWN ON THE PLAN DETAILS. THIS WORK SHALL BE INCLUDED IN THE COST OF THE BITUMINOUS SURFACE.

THE BASE COURSE WIDENING SHALL BE CARRIED THROUGH ALL ENTRANCES, SIDE ROADS, AND MAILBOX TURNOUTS. EXCEPTIONS WILL BE SHOWN ON THE PLANS.

EXCEPT AS NOTED ON THE PLANS, PAVEMENT GRADES SHOWN ARE AT THE TOP OF PAVEMENT SURFACES.

BEFORE ORDERING PIPE CULVERTS OR PIPE DRAINS, THE CONTRACTOR SHALL CONSULT THE ENGINEER FOR EXACT LENGTHS.

ESTIMATED QUANTITIES OF EXPLORATION TRENCH, STORM SEWER SPECIAL, AND FIELD TILE JUNCTION VAULTS HAVE BEEN INCLUDED IN THE PLANS. THESE ITEMS ARE NOT SCHEDULED. EXACT LOCATIONS FOR THESE ITEMS SHALL BE DETERMINED BY THE ENGINEER.

AGGREGATE (PRIME COAT): FA 20 MAY BE USED IN ADDITION TO THE GRADATIONS LISTED IN THE 3RD PARAGRAPH OF ARTICLE 1003.03(g) OF THE STANDARD SPECIFICATIONS.

THE ENGINEER WILL BE THE SOLE JUDGE CONCERNING CURING TIME FOR THE VARIOUS BITUMINOUS LIFTS.

FOR STABILIZATION, ALL TYPE III BARRICADES SHALL REQUIRE A MINIMUM OF FOUR SAND BAGS PER BARRICADE.

WHERE SECTION OR SUBSECTION MONUMENTS ARE ENCOUNTERED, THE ENGINEER SHALL BE NOTIFIED BEFORE SUCH MONUMENTS ARE REMOVED. THE CONTRACTOR SHALL PROTECT AND CAREFULLY PRESERVE ALL MONUMENTS UNTIL AN AUTHORIZED SURVEYOR OR AGENT HAS WITNESSED OR OTHERWISE REFERENCED THEIR LOCATION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR HAVING AN AUTHORIZED SURVEYOR REESTABLISH ANY SECTION OR SUBSECTION MONUMENTS DESTROYED BY HIS OPERATIONS.

SEEDING SHALL NOT BE PERMITTED AT ANY TIME WHEN THE GROUND IS FROZEN, WET, OR IN AN UNTILLABLE CONDITION. LOCATIONS TO BE SEEDED WILL BE DETERMINED BY THE ENGINEER.

ONLY THOSE TREES DESIGNATED BY THE ENGINEER OR LISTED IN THE TREE REMOVAL SCHEDULE SHALL BE REMOVED. THE CONTRACTOR SHALL PROTECT ALL REMAINING TREES FROM DAMAGE DUE TO HIS OPERATIONS.

THE FINISHED EARTHWORK SHALL HAVE A VEGETATION SUSTAINING SOIL COVERING THE TOP FOUR INCHES IN ALL AREAS TO BE SEEDED. THE VEGETATION SUSTAINING SOIL REQUIRED WILL NOT BE PAID FOR SEPARATELY, BUT SHALL BE INCLUDED IN THE COST OF EARTH EXCAVATION.

ALL ELEVATIONS REFER TO THE U.S.G.S. MEAN SEA LEVEL DATUM.

ABANDONED UNDERGROUND UTILITIES THAT CONFLICT WITH CONSTRUCTION SHALL BE DISPOSED OF OUTSIDE THE LIMITS OF THE RIGHT OF WAY ACCORDING TO ARTICLE 202.03 OF THE STANDARD SPECIFICATIONS AND AS DIRECTED BY THE ENGINEER. THIS WORK WILL NOT BE PAID FOR SEPARATELY BUT SHALL BE INCLUDED IN THE COST OF EARTH EXCAVATION.

ANY REFERENCE TO A STANDARD IN THESE PLANS SHALL BE INTERPRETED TO MEAN THE EDITION AS INDICATED BY THE SUBNUMBER LISTED ON THE INDEX OF SHEETS OR THE COPY OF THE STANDARD INCLUDED IN THESE PLANS.

THE FOLLOWING RATES OF APPLICATION HAVE BEEN USED IN CALCULATING PLAN QUANTITIES:

GRANULAR MATERIALS	2.05	TONS / CU YD
BITUMINOUS MAT PRIME COAT	0.08	GAL / SQ YD OR
	0.375	GAL / SQ YD
AGGREGATE PRIME COAT	0.002	TONS / SQ YD
BITUMINOUS RESURFACING	112	LBS / SQ YD / IN
SHORT TERM PAVEMENT MARKING	10	FT / 100 FT OF APPLICATION
TEMPORARY DITCH CHECKS	9	BALES OR
	5	TONS AGGREGATE

THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING UTILITY PROPERTY DURING CONSTRUCTION OPERATIONS AS OUTLINED IN ARTICLE 107.31 OF THE STANDARD SPECIFICATIONS. A MINIMUM OF 48 HOURS ADVANCE NOTICE IS REQUIRED FOR NON-EMERGENCY WORK. THE JULIE NUMBER IS 800-892-0123. THE FOLLOWING LISTED UTILITIES LOCATED WITHIN PROJECT LIMITS OR IMMEDIATELY ADJACENT TO PROJECT LIMITS ARE MEMBERS OF JULIE:

NICOR GAS COMPANY
1844 FERRY ROAD
NAPERVILLE, ILLINOIS 60563

VERIZON
1312 EAST EMPIRE STREET
BLOOMINGTON, ILLINOIS 61701

AMEREN IP
501 EAST LAFAYETTE STREET
BLOOMINGTON, ILLINOIS 61702

CORN BELT ENERGY
ONE ENERGY WAY
BLOOMINGTON, ILLINOIS 61704

MEDIACOM
1102 NORTH FOURTH STREET
CHILLICOTHE, ILLINOIS 61523

MAGELLAN MIDSTREAM PARTNERS
13424 WEST 98TH STREET
SHAWNEE MISSION, KANSAS 66215

THE FOLLOWING LISTED UTILITIES LOCATED WITHIN PROJECT LIMITS OR IMMEDIATELY ADJACENT TO PROJECT LIMITS ARE NON-MEMBERS OF JULIE:

VILLAGE OF DOWNS
211 S. SEMINARY
DOWNS, ILLINOIS 61736

COMMITMENTS:

- ENVIRONMENTAL COORDINATION.
- THE CONTRACTOR SHALL BE AWARE OF THE PRESENCE OF A SEPTIC SYSTEM IN THE PROXIMITY OF THE TEMPORARY EASEMENT IN THE SOUTHWEST QUADRANT OF THE WASHINGTON STREET INTERSECTION. CARE IS TO BE USED WHEN WORKING WITHIN THE TEMPORARY CONSTRUCTION EASEMENT SO AS NOT TO DAMAGE THE SEPTIC SYSTEM.
- DURING NEGOTIATIONS, A COMMITMENT WAS MADE TO RELOCATE THE EXISTING TURN AROUND OUTSIDE OF THE PROPOSED RIGHT-OF-WAY AREA AT STATION 695+52 LT. A TEMPORARY USE PERMIT WILL BE SECURED BY THE LAND ACQUISITION SECTION.

PLAN	DATE
BY	
SURVEYED	
ALIGNED	
CHECKED	
NOTE BOOK	
NO.	

PROFILE	DATE
BY	
SURVEYED	
GRADES	
CHECKED	
NOTE BOOK	
NO.	

COMPANY NAME: #COMPANY NAME
PROJECT CONTACT: #PROJECT CONTACT#
CLIENT: #CLIENT#
DATER: #DATER#
FILE#

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION DISTRICT THREE	
REVIEWED BY:	<i>Rich Powell</i> DISTRICT STUDIES AND PLANS ENGINEER
DATE:	2/9/06
EXAMINED BY:	<i>Robert J. [Signature]</i> DISTRICT CONSTRUCTION ENGINEER
	<i>Kenneth R. [Signature]</i> DISTRICT MATERIALS ENGINEER
	<i>James A. [Signature]</i> DISTRICT OPERATIONS ENGINEER

ILLINOIS DEPARTMENT OF TRANSPORTATION F.A.S. 1517 (U.S. ROUTE 150)	
GENERAL NOTES	
SCALE: VERT.	DRAWN BY
DATE	CHECKED BY