F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1517	(2)RS-3 (3)RS-4	MCLEAN	223	31
STA. _____		TO STA._____		
FED. ROAD DIST. NO. _	ILLINOIS	FED. AID PROJECT		

66383

TREE REMOVAL SCHEDULE

LOCATION			TREE REMOVAL (6 TO 15 UNITS) (UNITS)	TREE REMOVAL (OVER 15 UNITS) (UNITS)
408+08.28	42.3	LT	6	
408+12.91	46.1	LT	8	
408+13.80	39.9	LT	8	
408+14.95	50.3	LT	6	
408+18.28	42.6	LT	10	
408+23.36	42.8	LT	10	
408+36.15	39.2	LT	8	
408+51.67	47.3	LT		18
408+65.85	45.2	LT	6	
408+78.02	45.9	LT	6	
408+81.36	44.4	LT		36
409+00.94	40.5	LT		30
409+02.49	38.6	LT	12	
409+20.28	40.8	LT	6	
409+21.81	32.8	LT		22
409+23.61	33.3	LT	8	
409+26.39	34.5	LT	8	
409+38.56	31.5	LT	6	
414+27.17	28.8	RT		42
414+30.33	29.8	RT	6	
414+33.69	28.5	RT		24
414+39.55	30.4	RT	6	
414+62.63	31.0	RT	8	
414+96.14	35.4	RT	12	
415+05.66	34.3	RT	12	
504+08.67	31.4	RT	8	
601+37.83	48.3	RT		18
601+49.32	37.9	RT		24
603+42.45	41.8	RT		24
604+27.19	40.0	RT		24
606+11.97	33.4	RT		48
608+38.79	47.7	LT	6	
608+51.14	46.4	LT	6	
608+95.73	38.5	LT	8	
609+07.06	37.5	LT	8	
609+18.65	38.1	LT	10	
609+42.65	37.9	LT	6	
609+55.70	37.2	LT	8	
653+10.48	36.1	LT		48
653+64.59	38.8	LT		60
655+11.76	42.2	LT		36
660+53.12	29.9	RT		36
672+72.75	40.8	RT	8	
1303+66.84	16.9	LT	8	
1303+70.83	23.9	LT	8	
1303+78.52	33.1	RT		18
1303+85.63	25.2	LT	8	
SUBTOTAL			244	508
10% GROWTH FACTOR			24	51
TOTAL			268	559

EARTHWORK SCHEDULE

LOCATION	EARTH EXCAVATION (CU YD)	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (CU YD)	SECTION TOTALS EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)
U.S. ROUTE 150				
408+03 TO 424+00	208	156	1014	-858
424+00 TO 438+00	2354	1766	796	970
438+00 TO 510+00	17015	12761	2010	10751
510+00 TO 596+00	15496	11622	2971	8651
596+00 TO 627+00	8956	6717	678	6039
627+00 TO 641+00	1977	1483	511	972
641+00 TO 680+00	8443	6332	872	5460
680+00 TO 754+50	19536	14652	2462	12190
SUBTOTAL	73985	55489	11314	44175
SEMINARY STREET				
1100+00.00 TO 1101+31.14	46	35	11	24
C.H. 36 NORTH				
1203+00.00 TO 1210+00.00	2289	1717	211	1506
T.R. 2075				
1300+20.00 TO 1306+43.18	1638	1229	241	988
C.H. 36 SOUTH				
1500+00.00 TO 1502+56.21	498	374	13	361
T.R. 2200				
1601+00.00 TO 1602+98.36	285	214	3	211
T.R. 2325				
1700+00.00 TO 1702+50.00	69	52	72	-20
T.R. 2375				
1800+50.00 TO 1802+39.72	105	79	16	63
T.R. 2400				
1900+00.00 TO 1901+50.00	166	125	2	123
T.R. 2450				
2400+50.00 TO 2402+32.08	290	218	1	217
TOTAL	79371	59528	11884	47644

SHRINKAGE FACTORS

EARTH EXCAVATION 25%

ILLINOIS DEPARTMENT OF TRANSPORTATION

F.A.S. 1517 (U.S. ROUTE 150)

TREE REMOVAL SCHEDULE
EARTHWORK SCHEDULE

SCALE: VERT. HORIZ. DRAWN BY

DATE CHECKED BY

PLAN | SURVEYED | PLOTTED | ALIGNMENT CHECKED | DESIGN INPUT CHECKED | CADD FILE NAME | NOTE BOOK NO. | BY | DATE

PROFILE | SURVEYED | PLOTTED | GRADES CHECKED | STRUCTURE NOTATNS CHKD | NOTE BOOK NO. | BY | DATE

COMPANY NAME: SEA, INC.
PROJECT CONTACT: TONY SIMMONS
CLIENT: IDOT
DATE/TIME: 2/26/2009 6:56:55 PM
Y:\Jobs\Smith\2005\00124h\cad\fin-dwg\24_trees-ev.dgn