

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
311	IN & TS	KENDALL	174	18
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SEEDING & EROSION CONTROL SCHEDULE

LOCATION	AREA	SEEDING CL 2A	SEEDING CL 2	SODDING	SUPPL. WATERING	TEMPORARY EROSION CONTROL SEEDING	NITROGEN FERTILIZER	PHOSPHORUS FERTILIZER	POTASSIUM FERTILIZER	PERIMETER EROSION BARRIER	EROSION CONTROL BLANKET	INLET AND PIPE PROTECTION	TEMPORARY DITCH CHECK	MULCH METHOD 2
LOCATION	SQ. FT.	ACRE	ACRE	SQ. YD.	UNITS	POUNDS	POUNDS	POUNDS	POUNDS	FEET	SQ. YD.	EACH	EACH	ACRE
KENDALL COUNTY														
DETOUR														
STA 485+00 TO STA 495+50	20237					372				940	729	10	2	
FRONTAGE ROAD	6971.8	0.16				96	14	14	14	300			1	0.16
EXISTING IL 126														
STA 62+00 TO STA 67+50	23425		0.54				48	48	48	500				0.54
STA 77+21 TO STA 86+50	73870		1.70				153	153	153	430	26			1.70
RELOCATED IL 126														
STA 59+00 TO STA 80+44	110887.7	2.55				1527	229	229	229	3180	71	2	7	2.55
STA 81+45 TO STA 99+32.63	70165.7	1.61		2452	7	967	175	175	175	350	41 X 3 BOXES	12	5	1.61
IL 71														
STA 559+88 TO STA 566+47	15209.7	0.35				210	31	31	31				2	0.35
STA 566+47 TO STA 572+00	27151.3	0.62				374	56	56	56	310			2	0.62
STA 572+00 TO STA 584+05	55423.5	1.27				763	115	115	115	745	71		3	1.27
LINE TOTAL		6.56	2.23	2452	7	4309	822	822	822	6755	1020	24	22	8.79

1. NOTE: QUANTITY FOR TEMPORARY SEEDING AVAILABLE FOR 6 APPLICATIONS

REMOVAL SCHEDULE

LOCATION	LENGTH	PAVEMENT REMOVAL	ISLAND PAV'T REM.	REMOVE EXIST. STRUCTURE NO. 1	REMOVE EXIST. STRUCTURE NO. 2	REMOVE EXIST. STRUCTURE NO. 3	REMOVE MANHOLES	PIPE CULVERT REM.	FENCE REMOVAL	BITUMINOUS SURFACE REMOVAL VAR. DEPTH	BITUMINOUS SURFACE REMOVAL BUTT JOINT	BITUMINOUS SURFACE REMOVAL 1 1/2"	BITUMINOUS SURFACE REMOVAL 2 1/4"
STATION	FOOT	SQ. YD.	SQ. YD.	EACH	EACH	EACH	EACH	FOOT	FOOT	SQ. YD.	SQ. YD.	SQ. YD.	SQ. YD.
EXIST. IL 126													
STA. 59+00 TO STA. 59+60	60										173.3		
STA. 60+91.56 TO STA. 67+50	658.44	1902.2							658				
STA. 67+50 TO STA. 74+73.8	723.8											2517	
STA. 74+73.8 TO STA. 76+70	196.2	546.3	91.1										
STA. 76+70 TO STA. 91+54	1584	5777.7	78.1				2	150		2226.7			
STA 82+75						1							
STA 89+90				1									
STA 91+54 TO STA. 98+51.57	697.57							117					2015.2
PROP IL 126													
EXIST. IL 71													
STA. 559+87.26 TO STA. 560+47.26	60										160		
STA. 567+15.7 TO STA. 568+77	161.3	SEE IL 126 ABOVE								735.5			
STA. 559+87.26 RT TO STA. 563+96.1 RT	408.8	361.6								597.4			
STA. 568+77.3 RT TO STA. 570+16.8 RT	139.3	131.4							139.3	310.7			
STA. 570+16.8 RT TO STA. 573+78.2 RT	360.6	226.2							360.6	490			
STA. 573+78.2 RT TO STA. 581+00 RT	721.8	160.4							323				
STA 578+22					1								
STA. 573+78.2 LT TO STA. 583+00 LT	921.8	73.1								1276.6			
STA. 583+45.21 TO STA. 584+05.21	60										160		
TOTAL		9178.9	169.2	1	1	1	2	267	2356	5636.9	493.3	2517	2015.2

\* VARIABLE DEPTH REMOVAL FOR CROWN CORRECTION ON IL 71  
STA. 570+50 TO STA 572+00 VARIABLE DEPTH REMOVAL FOR PROFILE CHANGE ON IL 71 (4" MAX)

RUNAROUND SCHEDULE

LOCATION	LENGTH	BITUMINOUS BASE CSE 9 1/2'	PAVEMENT REMOVAL	BIT. SHLDR REM	SUB BASE GRAN MAT. TYPE A 12"	AGG. FOR TEMP. ACCESS	TEMPORARY PIPE CULV. CL D, TY1 24"	TEMPORARY PIPE CULV. CL D, TY1 15"	TEMPORARY PIPE CULV. CL D, TY1 12"	BITUMINOUS SHOULDER 6"	TEMPORARY PAVEMENT MARKING 4"		PAVEMENT MARKING REMOVAL
											WHITE	YELLOW	
	FOOT	SQ YD	SQ YD	SQ YD	SQ YD	TON	FOOT	FOOT	FOOT	SQ YD	FOOT	FOOT	FOOT
STA 484+50 TO STA. 497+00	1250	2210.7	2210.7	814	2284					813.6	2500	2500	685
STA. 486+12 RT						15.6		41					
STA. 488+40 RT						15.9		26					
STA. 489+88 RT						9	56						
STA. 491+68 RT						23.1			30				
STA. 493+68 RT						9.3			36				
STA. 495+70 RT							36						
TOTAL		2210.7	2210.7	814	2284	72.9	92	67	66	813.6	5000		685

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	

**SCHEDULES**

SCALE: VERT. \_\_\_\_\_ HORIZ. \_\_\_\_\_  
DATE \_\_\_\_\_ DRAWN BY \_\_\_\_\_ CHECKED BY \_\_\_\_\_

3/21/2006 01:10:09 Recv: 590028004.sch: 200/185.dgn