

FAP RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
317	(25B-1)I	LIVINGSTON	21	4
STA. 472+94.25		TO STA. 474+79.75		

STAGE CONSTRUCTION	PAVEMENT MARKING REMOVAL	TEMPORARY PAVEMENT MARKING LINE 4"	TEMPORARY PAVEMENT MARKING LINE 24"	WORK ZONE PAVEMENT MARKING REMOVAL
	SQ FT	FOOT	FOOT	SQ FT
STAGE I	264	762	80	411
STAGE II		772		255
TOTAL	264	1534	80	666

STAGE CONSTRUCTION	FLOOR DRAIN EXTENSION	PLUG EXISTING FLOOR DRAINS
	EACH	EACH
STAGE I	20	12
STAGE II	20	12
TOTAL	40	24

STAGE CONSTRUCTION	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)
	EACH	EACH	EACH
STAGE I	10		
STAGE II		7	3
TOTAL	10	7	3

STAGE CONSTRUCTION	WATERPROOFING MEMBRANE SYSTEM
	EACH
STAGE I	349
STAGE II	349
TOTAL	698

STAGE CONSTRUCTION	SILICONE JOINT SEALER 1 3/4"
	FOOT
STAGE I	37
STAGE II	37
TOTAL	74

STAGE CONSTRUCTION	BITUMINOUS CONCRETE SURFACE REMOVAL	BITUMINOUS CONCRETE SURFACE COURSE SUPERPAVE MIX D, N70	POLYMER CONCRETE
	SQ YD	TON	CU FT
STAGE I	359	53	2.6
STAGE II	339	57	2.6
TOTAL	698	110	5.2

STAGE CONSTRUCTION	TEMPORARY CONCRETE BARRIER
	FOOT
STAGE I	425
STAGE II	
TOTAL	425

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULES
FAP ROUTE 317 SECTION (25B-1)I
LIVINGSTON COUNTY
STA. 473 + 87

DATE: 09/27/2005
 FILE: c:\projects\cme06\cm322\detail.dgn