

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	(27-38)I-1 & (27-1)I-2	FORD	14	3
ILLINOIS				

SUMMARY OF QUANTITIES

CONSTRUCTION CODE: **J000**

RURAL

100% STATE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	SECTION (27-38)I-1	SECTION (27-1)I-2
20200100	EARTH EXCAVATION	CU YD	716		716
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	781		781
42100330	CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT 11 1/2"	SQ YD	781		781
42100930	PAVEMENT REINFORCEMENT 11 1/2"	SQ YD	781		781
44001430	BITUMINOUS SHOULDER REMOVAL	SQ YD	879		879
44002100	CONTINUOUSLY REINFORCED CONCRETE PAVEMENT REMOVAL	SQ YD	781		781
44212899	PAVEMENT PATCHING (FULL DEPTH)	SQ YD	360	48	312
44213000	PATCHING REINFORCEMENT	SQ YD	360	48	312
44213200	SAW CUTS	FOOT	2604	360	2244
48101200	AGGREGATE SHOULDERS TYPE B	TON	44		44
48202830	BITUMINOUS SHOULDERS SUPERPAVE 11 1/2"	SQ YD	879		879
60107800	PIPE UNDERDRAINS 8"	FOOT	771		771
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	24		24
60108300	PIPE UNDERDRAINS 8" (SPECIAL)	FOOT	24		24
64200105	SHOULDER RUMBLE STRIPS	FOOT	791		791
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CALMO	2		2
67100100	MOBILIZATION	L SUM	1		1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
FAI 57
SEC: (27-38)I-1 & (27-1)I-2
FORD COUNTY

Date: April 5, 2006
File Name: ar/projects/consair07/cons07/dsall.dgn