

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	(27-38)I-1 & (27-1)I-2	FORD	14	8
ILLINOIS				

DRAINAGE SCHEDULE AT S.N. 027-0048

LOCATION BY STATIONING	CONCRETE HEADWALL FOR PIPE UNDERDRAIN REMOVAL	PIPE UNDERDRAIN REMOVAL	PIPE UNDERDRAIN 8"	PIPE UNDERDRAIN 4" (SPECIAL)	PIPE UNDERDRAIN 8" (SPECIAL)	REMOVE & REINSTALL CONCRETE HEADWALL FOR PIPE UNDERDRAINS
	EACH	FOOT	FOOT	FOOT	FOOT	EACH
255+55 TO 255+87		32	32			
255+87 TO 255+90		3	3			
255+55				24		1
255+90 TO 258+66		276	276			
257+51		24				
258+66 TO 259+01		35	35			
259+01 TO 261+70		269	269			
261+46	1	24				
261+70 TO 261+73		3	3			
261+73 TO 263+26		153	153			
263+26					24	1
TOTAL	1	819	771	24	24	1

STAGING SCHEDULE AT S.N. 027-0048

LOCATION	PAVEMENT MARKING REMOVAL	WORKZONE PAVEMENT MARKING REMOVAL	TEMPORARY CONCRETE BARRIER
	SQ FT	SQ FT	FOOT
STA 252+45 TO STA 284+36	1537	1775	1170
TOTALS	1537	1775	1170

REMOVAL SCHEDULE AT S.N. 027-0048

LOCATION	EARTH EXCAVATION	BITUMINOUS SHOULDER REMOVAL	CRC PAVEMENT REMOVAL
	CU YD	SQ YD	SQ YD
STA 254+45 TO STA 264+35	716	879	781
TOTALS	716	879	781

PAVEMENT MARKING SCHEDULE

LOCATION	EPOXY PAVEMENT MARKING LINE 4"	EPOXY PAVEMENT MARKING LINE 6"	45 MIL HOT SPRAY THERMOPLASTIC PAVEMENT MARKING LINE 4"	45 MIL HOT SPRAY THERMOPLASTIC PAVEMENT MARKING LINE 6"	RAISED REFLECTIVE PAVEMENT
	FOOT	FOOT	FOOT	FOOT	MARKER
	WHITE	WHITE	WHITE	WHITE	CRYSTAL
STA 254+45 TO STA 264+35	2390	990			24
PATCHING LOCATIONS			270	70	16
TOTALS	2390	990	270	70	40

REPLACEMENT SCHEDULE AT S.N. 027-0048

LOCATION	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	AGGREGATE SUBGRADE 18"	STABILIZED SUB-BASE 4" SUPERPAVE	PAVEMENT REINFORCEMENT 11 1/2"	DRILL & GROUT #6 TIE BARS	CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT 11 1/2"	BITUMINOUS SHOULDERS SUPERPAVE 11 1/2'	SHOULDER RUMBLE STRIPS	AGGREGATE SHOULDERS TYPE B
	SQ YD	SQ YD	SQ YD	SQ YD	EACH	SQ YD	SQ YD	FOOT	TON
STA 254+45 TO STA 264+35	1660	1432	912	781	235	781	879	791	44
TOTALS	1660	1432	912	781	235	781	879	791	44

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SCHEDULES AT S.N. 027-0048**  
 FAI 57  
 SEC: (27-38)I-1 & (27-1)I-2  
 FORD COUNTY  
 DATE 04/05/2006  
 DRAWN BY RLW

Date: Apr 15, 2006  
 File Name: c:\projects\cmanr027\m300\deln1a.dgn