CLASS A PATCHING WESTBOUND LANES

LOCATION BY LOG MILE	PASSING LANE			DRIVING LANE			REMARKS
	CLASS A PATCHING TYPE II 10"	PATCHING REINFORCEMENT	SAW CUTS	CLASS A PATCHING TYPE II 10"	PATCHING REINFORCEMENT	SAW CUTS	
	SQ YD	SQ YD	FOOT	SQ YD	SQ YD	FOOT	
RURAL SECTION							
0.00							CENTERLINE IL ROUTE 1
0.01	8	8	66	8	8	66	
0.05	8	8	66				
0.11	8	8	66	8	8	66	
0.18	8	8	66				
0.19	8	8	66	8	8	66	
0.20	8	8	66	8	8	66	
0.26	8	8	66	8	8	66	CENTERLINE SUNSET ROAD
0.81							CENTERLINE N. RIVERWOOD ROAD
1.28							CENTERLINE S. HEILAND ROAD
1.38	8	8	66	8	8	66	
1.46	8	8	66	8	8	66	
1.56	8	8	66	8	8	66	
1.66				8	8	66	
1.70							CENTERLINE N. EAGLE ISLAND ROAD
1.75				8	8	66	
2.33	8	8	66	8	8	66	
2.34							CENTERLINE EXLINE ROAD
2.36				8	8	66	
2.42	8	8	66	8	8	66	
2.48	8	8	66	8	8	66	
3.08	8	8	66	8	8	66	
3.43	8	8	66	8	8	66	
3.56	8	8	66	8	8	66	
3.62	8	8	66	8	8	66	
SUBTOTAL	136	136	1122	144	144	1188	
URBAN SECTION							
3.82							CENTERLINE SKYLINE ROAD
4.50				8	8	66	
4.62							AROMA PARK ROAD
4.79	8	8	66	8	8	66	
4.85	8	8	66	8	8	66	
4.86				8	8	66	
5.05				8	8	66	
5.09	8	8	66	8	8	66	
5.11							CENTERLINE SPLEAR ROAD
5.33	8	8	66				
5.38	8	8	66				
5.39				8	8	66	
5.44							CENTERLINE EASTGATE INDUSTRIAL PARK ROAD
5.46	8	8	66	8	8	66	
5.48	8	8	66				
5.56				8	8	66	
5.60				8	8	66	
5.61				8	8	66	
5.65	8	8	66	8	8	66	
5.68				8	8	66	
5.78							CENTERLINE EASTRIDGE ROAD
SUBTOTAL	64	64	528	104	104	858	
TOTAL	200	200	1650	248	248	2046	

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

PATCHING SCHEDULES

WESTBOUND LANE

FAP 41 (IL 17)

SECTION: (1R)I

KANKAKEE COUNTY

Date: April 25, 2006
File Name: c:/projects/cmsun07/cm318/details.dgn