

RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
•	(7R-1,10)I	KANKAKEE	11	3
STA. 248+00		TO STA. 259+00		
ILLINOIS				

*FAP 332 & FAS 310 (IL 1 & IL 17)

SUMMARY OF QUANTITIES

CONSTRUCTION CODE: **1000-1A**

CODE NO.	ITEM	UNIT	RURAL
			100% STATE TOTAL QUANTITY
20200500	EARTH EXCAVATION (WIDENING)	CU YD	25
20400800	FURNISHED EXCAVATION	CU YD	7
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	183
35400900	HIGH-EARLY-STRENGTH PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 9"	SQ YD	160
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	71
44000035	BITUMINOUS SURFACE REMOVAL	SQ YD	30
44000100	PAVEMENT REMOVAL	SQ YD	30
44000300	CURB REMOVAL	FOOT	90
44001430	BITUMINOUS SHOULDER REMOVAL	SQ YD	135
44200132	PAVEMENT PATCHING, TYPE II, 11 INCH	SQ YD	596
44200136	PAVEMENT PATCHING, TYPE III, 11 INCH	SQ YD	101
44200138	PAVEMENT PATCHING, TYPE IV, 11 INCH	SQ YD	34
44213100	PAVEMENT FABRIC	SQ YD	134
44213200	SAW CUTS	FOOT	3659
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	228
48202600	BITUMINOUS SHOULDERS SUPERPAVE 8"	SQ YD	72
67100100	MOBILIZATION	L SUM	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1
* 78005110	EPOXY PAVEMENT MARKING LINE - 4"	FOOT	100
* 78005140	EPOXY PAVEMENT MARKING LINE - 8"	FOOT	100
* 78005150	EPOXY PAVEMENT MARKING LINE - 12"	FOOT	100
X4066428	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N90	TON	18
Z0017202	DOWEL BARS 1 1/2"	EACH	1854

* SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
FAP 332 & FAS 310
SECTION (7R-1,10)I
KANKAKEE COUNTY

Date: 4/21/2006
cs/projects/cmain07/cm311/details.dgn