

RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
•	••	LIVINGSTON	10	3

• DWIGHT MAINTENANCE YARD  
 •• (DWIGHT MAINTENANCE YARD)T

# SUMMARY OF QUANTITIES

CONSTRUCTION CODE TYPE: X028-2A

**URBAN**  
 100% STATE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY
20400800	FURNISHED EXCAVATION	CU YD	350
20700220	POROUS GRANULAR EMBANKMENT	CU YD	245
31102900	SUB-BASE GRANULAR MATERIAL (SPECIAL)	CU YD	81
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	275
54001000	BOX CULVERT END SECTIONS	EACH	2
54002050	EXPANSION BOLTS 3/4 INCH X 9 INCH	EACH	192
54021010	PRECAST CONCRETE BOX CULVERT 10' X 10' (M273)	FOOT	36
67100100	MOBILIZATION	L SUM	1

DATE: March 27, 2006  
 FILE: c:\projects\cma1n07\cm315\detail is.dgn

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SUMMARY OF QUANTITIES**  
 (DWIGHT MAINTENANCE YARD)T  
 LIVINGSTON COUNTY  
 S.N. 053-2041

DATE: 02/24/2006

DRAWN BY: RW