

**GENERAL NOTES**

THE TRAFFIC CONTROL REQUIRED FOR THE INSTALLATION OF TREES SHALL BE CONSIDERED INCIDENTAL TO THE VARIOUS PAY ITEMS OF WORK, AND SHALL BE IN ACCORDANCE WITH THE TRAFFIC CONTROL STANDARDS INCLUDED WITHIN.

ALL WORK ( EXCAVATING, BACKFILLING, WRAPPING, BRACING, WATERING, MULCHING, ETC.) REQUIRED FOR THE INSTALLATION OF TREES SHALL BE CONSIDERED INCLUDED IN THE COST OF THE VARIOUS TREE PAY ITEMS.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING UTILITY PROPERTY FROM CONSTRUCTION OPERATIONS AS OUTLINED IN ARTICLE 107.31 OF THE STANDARD SPECIFICATIONS. THE J.U.L.I.E. NUMBER IS 1-800-892-0123. A MINIMUM OF FORTY-EIGHT HOURS ADVANCE NOTICE IS REQUIRED.

THE CONTRACTOR'S ATTENTION IS DIRECTED TO THE PRESENCE OF DEPARTMENT-OWNED UNDERGROUND ELECTRICAL CABLE WITHIN THE LIMITS OF THE PROPOSED IMPROVEMENT. THE CONTRACTOR SHALL REQUEST THE ILLINOIS DEPARTMENT OF TRANSPORTATION IN OTTAWA (815-434-8417) TO LOCATE THE UNDERGROUND FACILITIES, PROVIDING A MINIMUM OF 72 HOURS NOTICE. THE DEPARTMENT IS NOT A MEMBER OF THE JOINT UTILITY LOCATING INFORMATION FOR EXCAVATORS (JULIE) SYSTEM.

ALL DAMAGE TO DEPARTMENT OWNED UNDERGROUND FACILITIES, CAUSED BY THE CONTRACTOR SHALL BE REPAIRED TO THE SATISFACTION OF THE DEPARTMENT AT THE CONTRACTOR'S EXPENSE. THIS SHALL INCLUDE ALL TEMPORARY REPAIRS REQUIRED TO KEEP THE FACILITY OPERATIONAL WHILE MATERIAL IS BEING OBTAINED TO MAKE PERMANENT REPAIRS. SPLICING OF ELECTRIC CABLE SHALL NOT BE ALLOWED. ELECTRIC CABLE SHALL BE REPLACED FROM POLE TO POLE OR CONTROLLER.

ANY REFERENCE TO A STANDARD IN THESE PLANS SHALL BE INTERPRETED TO MEAN THE EDITION AS INDICATED BY THE SUBNUMBER LISTED ON THE INDICES OF SHEETS OR THE COPY OF THE STANDARD INCLUDED IN THESE PLANS.

SPECIAL CARE IS NEEDED IN EXSITING WILDFLOWER PLOTS, THE ENGINEER SHALL BE CONTACTED 48 HRS PRIOR TO EXCAVATION.

F. A. REF.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	●	VAR.	4	2
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

● D-3 TREE PLANTING 2007  
CONTRACT #66675

SUMMARY OF QUANTITIES				100% STATE	
CODE NO.	ITEM	UNIT	TOTAL	Y003	Y003
				KENDALL CO.	LASALLE CO.
A2000116	TREE, ACER X FREEMANII AUTUMN BLAZE (AUTUMN BLAZE FREEMAN MAPLE), 2" CALIPER, BALLED AND BURLAPPED	EACH	20	20	
A2002916	TREE, CELTIS OCCIDENTALIS (COMMON HACKBERRY), 2" CALIPER, BALLED AND BURLAPPED	EACH	451		451
67100100	MOBILIZATION	L SUM	1	0.1	0.9

TREE PLANTING - KENDALL COUNTY			
STATION TO STATION	SIDE	TREE TYPE	QUANTITY
US 34 - PLANO			
164+50 TO 167+50	RT	AUTUMN BLAZE	20
TOTAL			20

TREE PLANTING - LASALLE COUNTY			
STATION TO STATION	SIDE	TREE TYPE	QUANTITY
I-39			
955+00 TO 997+50	NBL	HACKBERRY	143
955+00 TO 997+50	SBL	HACKBERRY	143
937+50 TO 947+50	NBL	HACKBERRY	34
937+50 TO 947+50	SBL	HACKBERRY	34
250+00 TO 260+00	SBL	HACKBERRY	67
US RT 6			
127+00 TO 136+00	SBL	HACKBERRY	30
TOTAL			451

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION  
DISTRICT THREE

PREPARED BY: Rick Powell  
DISTRICT STUDIES & PLANS ENGINEER

DATE: March 30, 2006

EXAMINED BY: Shabazz  
DISTRICT CONSTRUCTION ENGINEER

Ken Lang  
DISTRICT MATERIALS ENGINEER

Bruce A. Hoken  
DISTRICT OPERATIONS ENGINEER

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**GENERAL NOTES,  
SUMMARY OF QUANTITIES,  
& SCHEDULES**