

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
39	(50-4B)I-4	LASALLE	17	2
FED. ROAD DIST. NO.		ILLINOIS	NON-FED. AID PROJECT	

GENERAL NOTES:

Plan dimensions and details relative to the existing roadway and structure have been taken from existing plans and are subject to nominal construction variations. It shall be the contractor's responsibility to verify such dimensions and details in the field and to make necessary approved adjustments prior to construction or ordering of materials. Such variations shall not be cause for additional compensation for a change in the scope of the work, however, the contractor will be paid for the quantity actually furnished at the unit price bid for the work.

The contractor shall be responsible for protecting utility property from construction operations as outlined in Article 107.31 of the Standard Specifications. The "Julie" Number is 1-800-892-0123. A minimum of forty-eight (48) hours advance notice is required.

The cost of any saw cuts made to complete the work as described in plan details, unless otherwise noted shall not be paid for separately but shall be included in the various pay items involved.

For stabilization, all Type III barricades shall require a minimum of four sand bags per barricade.

Where section or subsection monuments are encountered, the engineer shall be notified before such monuments are removed. The contractor shall protect and carefully preserve all monuments until an authorized surveyor or agent has witnessed or otherwise referenced their location. The contractor shall be responsible for having an authorized surveyor reestablish any section or subsection monuments destroyed by his operations.

Any reference to a standard in these plans shall be interpreted to mean the edition as indicated by the subnumber listed on the index of sheets or the copy of the standard included in these plans.

Prior to pouring the new concrete deck, all loose rust, loose mill scale, and other loose potentially detrimental foreign material shall be removed from the surfaces of the beams or girders in contact with concrete. The cost of this work will be included in the pay item covering removal of the existing concrete. All heavy rust and other tightly adhered potentially detrimental foreign matter shall also be removed from the surfaces of the beams or girders in contact with concrete. Tightly adhered paint may remain unless otherwise noted. This removal shall be accomplished by methods that will not damage the steel. The cost of this work will be paid for according to Article 109.04 of the Standard Specifications.

New Reinforcement bars shall be Epoxy Coated.

Reinforcement bars that are to remain in place which are damaged during concrete removal operations shall be repaired or replaced using approved bar splicer or anchorage system. Cost included with "Concrete Removal".

Reinforcement bars shall conform to the requirements of AASHTO M 31 or M322 Grade 60.

ULTRA-THIN BONDED WEARING COURSE	
PG GRADE	SBSPG70-22
MIXTURE COMPOSITION	3/8" TYPE B CA/CM13 NOT ALLOWED
FRICITION AGGREGATE	MIXTURE D
WEARING COURSE THICKNESS	APPROXIMATELY 3/4" TYPICALLY 1.5 TO 2 X NOMINAL MAXIMUM AGGREGATE SIZE

PREPARED BY: *Rid Powell*
DISTRICT STUDIES & PLANS ENGINEER

DATE: 5-18-06

EXAMINED BY: *Harold Spang*
DISTRICT CONSTRUCTION ENGINEER

Matt Jacob
DISTRICT MATERIALS ENGINEER

Bruce A. Tucker
DISTRICT OPERATIONS ENGINEER

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

GENERAL NOTES
I-39 OVER THE ILLINOIS RIVER
F.A.I. ROUTE 39
SECTION: (50-4B)I-4
LASALLE COUNTY
S.N. 050-0191

DATE: 05/01/2006
C:\PROJECTS\2006\LASALLE\ABE\LINCOLN\66678\DETAILS.DWG