

F.A.P. RLE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
701	(128BRII-1	TAZEWELL	30	4
STA. 77+63.98		TO STA. 78+48.02		
FED. ROAD DIST. NO. 4 ILLINOIS FED. AID PROJECT				

SUMMARY OF QUANTITIES

CONSTRUCTION TYPE CODE

CODE NO.	ITEM	UNIT	CONSTRUCTION TYPE CODE		TOTAL
			X080-2A	SFTY -3N	
			100% STATE		
20300100	CHANNEL EXCAVATION	CU. YD.	1090		1090
20400800	FURNISHED EXCAVATION	CU. YD.	76		76
25000300	SEEDING, CLASS 3	ACRE	0.03		0.03
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	3		3
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	3		3
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	3		3
25100630	EROSION CONTROL BLANKET	SQ. YD.	152		152
28000400	PERIMETER EROSION BARRIER	FOOT	92		92
28100109	STONE RIPRAP, CLASS A5	SQ. YD.	183		183
28200200	FILTER FABRIC	SQ. YD.	1067		1067
28400100	GABIONS	CU. YD.	339		339
28401000	SLOPE MATTRESS 12"	SQ. YD.	479		479
31102000	SUB-BASE GRANULAR MATERIAL, TYPE C	CU. YD.	608		608
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	148		148
40600300	AGGREGATE (PRIME COAT)	TON	1		1
40600980	BITUMINOUS SURFACE REMOVAL-BUTT JOINT	SQ. YD.	160		160
48101200	AGGREGATE SHOULDERS, TYPE B	TON	2		2
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1		1
50300225	CONCRETE STRUCTURES	CU. YD.	6		6
50300260	BRIDGE DECK GROOVING	SQ. YD.	273		273

PLOT DATE *
 FILE NAME *
 PLOT SCALE *
 REFERENCE *

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
 SCALE: VERT. DRAWN BY CEJ
 DATE 03-24-2006 CHECKED BY