

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1671		DOUGLAS	181	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

• 1445BR-2 & 22VBR-1

## SUMMARY OF QUANTITIES

SHEET 1 OF 4

LOCATION OF WORK:  
FUNDING BREAKOUT  
CONSTRUCTION TYPE CODE:

	FAS 1671 RURAL 2L2W FED 80% STATE 20% 1000-2A 1124+40 - 1130+20.93 1131+24.93 - 1139+69.33 1139+69.33 - 1150+67.00 1155+98.5 - 1165+50.00	FAS 1671 BRIDGE SN 021-0062 FED 80% STATE 20% X280-2A 1130+20.93 TO 1131+24.93	<b>X181-5B</b> FAS 1671 BRIDGE SN 021-0061 FED 80% STATE 20% X181-2A 1150+67.00 TO 1152+69.00	<b>X171-5B</b> FAS 1671 BRIDGE SN 021-0060 FED 80% STATE 20% X171-2A 1154+06.5 TO 1155+98.50
--	--	--	--	---

CODE NO	ITEM	UNIT	TOTAL QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	102.0	102.0			
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	172.0	172.0			
20200100	EARTH EXCAVATION	CU YD	870.0	870.0			
20200500	EARTH EXCAVATION (WIDENING)	CU YD	60.0	60.0			
20400100	BORROW EXCAVATION	CU YD	88,330.0	88,330.0			
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	345.0		74.0	161.0	110.0
20800150	TRENCH BACKFILL	CU YD	13.0	13.0			
25000200	SEEDING, CLASS 2	ACRE	6.0	6.0			
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	540.0	540.0			
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	540.0	540.0			
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	540.0	540.0			
25100115	MULCH, METHOD 2	ACRE	6.0	6.0			
25100630	EROSION CONTROL BLANKET	SQ YD	11,879.0	11,879.0			
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	3,000.0	3,000.0			
28000300	TEMPORARY DITCH CHECKS	EACH	10.0	10.0			
28000400	PERIMETER EROSION BARRIER	FOOT	2,632.0	2,632.0			
28000500	INLET AND PIPE PROTECTION	EACH	3.0	3.0			
28100105	STONE RIPRAP, CLASS A3	SO YD	27.5	27.5			
30200650	PROCESSING MODIFIED SOILS 12"	SO YD	5,180.0	5,180.0			
30201500	LIME	TON	116.6	116.6			
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SO YD	233.0	233.0			
31102200	SUB-BASE GRANULAR MATERIAL, TYPE C 5"	SO YD	1,528.0	1,528.0			
35400300	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 8"	SO YD	155.0	155.0			
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	933.5	933.5			
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	639.0	639.0			
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SO YD	846.0	846.0			
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	106.0	106.0			
40800040	INCIDENTAL BITUMINOUS SURFACING	TON	156.0	156.0			
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SO YD	207.0	207.0			
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SO YD	680.0	680.0			
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SO YD	334.0	334.0			

• SPECIALTY ITEMS

PLOT DATE : 7/13/2006  
 FILE NAME : G:\projects\40505202 (W\170258)text.dgn  
 PLOT SCALE : 42.3543 / IN.  
 USER NAME : BIRSONDR

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

F.A.S. ROUTE 1671 (U.S. ROUTE 45)  
SECTION 1445BR-2 & 22VBR-1  
DOUGLAS COUNTY  
Sheet 1 of 4

SCALE: NOT TO SCALE  
DATE: 06/20/06

DRAWN BY: B.B.P.  
CHECKED BY: C.R.G.