

# SCHEDULE OF QUANTITIES

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
500	•	VERMILION	18	8

• (33,116 SPURRS-1  
CONTRACT NO. 70556

BITUMINOUS SURFACE REMOVAL ( BUTT JOINT)					
STA.	TO STA	WIDTH FT	LENGTH FT	AREA SQ YD	
URBAN	53+57.00	53+82.00	24	25	66.67
RURAL	177+41.50	177+66.5	33	25	91.67
	178+61.50	178+86.5	33	25	91.67
	261+95.50	262+20.5	30	25	83.33
	263+13.50	263+38.5	30	25	83.33
	102+75.00	103+00.0	24	25	66.67
	166+00.00	166+25.0	24	25	66.67
	173+50.00	173+75.0	24	25	66.67
				TOTAL	616.7 SOYDS
				USE	617.0 SOYDS

PERMANENT SURVEY MARKERS TO BE ADJUSTED			
RURAL	STA	DESCRIPTION	EACH
	162+86.94	W 1/4 SEC. 33	1
	189+34.42	NW COR SEC. 33-21-11	1
			TOTAL
			2 EACH

SURVEY MARKER VAULT				
URBAN	RURAL	STA	DESCRIPTION	EACH
		79+63.04	W 1/4 SEC. 10-20-11	1
		106+18.11	NW COR SEC. 10-20-11	1
		128+35.15	PC	1
		131+35.15	PI	1
		134+35.10	PT	1
		140+35.33	PI	1
		186+34.42	PC	1
		192+34.42	PI	1
		269+42.93	PI	1
			TOTAL	9 EACH

TEMPORARY RAMP						
URBAN	RURAL	STA.	TO STA	WIDTH FT	LENGTH FT	AREA SQ YD
		53+57.00	53+61.17	24	4.2	11.11
		177+62.33	177+66.50	33	4.2	15.28
		178+61.50	178+65.67	33	4.2	15.28
		262+16.33	262+20.50	30	4.2	13.89
		263+13.50	263+17.67	30	4.2	13.89
		102+95.83	103+00.00	24	4.2	11.11
		166+00.00	166+04.17	24	4.2	11.11
		173+70.83	173+75.00	24	4.2	11.11
					TOTAL	102.8
					USE	103.0

PAVMENT MARKINGS & MARKERS														
URBAN	RURAL	STA.	TO STA	LENGTH FT	PAINT PVMT MARK LINE, 4" LT. EDGE C. L. SKIP RT. EDGE LINE DASH LINE			SHORT TERM PVMT MARKINGS C. L. SKIP DASH 2 AP FT		WORK ZONE PVMT MARKER REMOVAL C. L. SKIP DASH 2 AP SOFT		RAISED REFL PVMNT MKRS EACH	RAISED REFL PVMNT MKRS REMOVAL EACH	URBAN
		53+57.00	106+12.70	5,255.70	5,255.70	1,313.93	5,255.70	525.57	175.19	66	66	URBAN		
		106+12.70	175+28.00	6,915.30	6,915.30	1,728.83	6,915.30	691.53	230.51	86	86	RURAL		
		175+28.00	177+66.50	238.50	238.50	59.63	238.50	23.85	7.95	3	3			
		178+61.50	180+98.00	236.50	236.50	59.13	236.50	23.65	7.88	3	3			
		180+98.00	253+05.23	7,207.23	7,207.23	1,801.81	7,207.23	720.72	240.24	90	90			
		253+42.87	258+97.00	554.13	554.13	138.53	554.13	55.41	18.47	7	7			
		258+97.00	262+20.50	323.50	323.50	80.88	323.50	32.35	10.78	4	4			
		263+13.50	266+33.00	319.50	319.50	79.88	319.50	31.95	10.65	4	4			
		266+33.00	269+42.93	309.93	309.93	77.48	309.93	30.99	10.33	4	4			
		100+00.00	103+00.00	300.00	300.00	75.00	300.00	30.00	10.00	4	4			
		166+00.00	173+75.00	775.00	775.00	193.75	775.00	77.50	25.83	10	10			
				TOTAL LENGTH	22,435.29	22,435.29	5,608.82	22,435.29	2,243.53	747.84	280	280		
					TOTAL	50,479.4 FEET	( X2 APPS) 4,487.06	( X2 APPS) 1,495.69	TOTAL	280 EACH	TOTAL	280 EACH		
					USE	50,479.0 FEET	TOTAL	4,488.0 FEET	TOTAL	1,496.0 SQFT				