F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	***	310	3
STA.		TO STA.		
CONTRACT NO. 74155				

* PARK ROADS
** SFWA PARK ROADS 2003-1
*** MOULTRIE AND SHELBY

SUMMARY OF QUANTITIES

CODED NO	DESCRIPTION	UNIT	QUANTITY	SHELBY CO. CONSTRUCTION CODE: MARGARET GUZY POTHOLE WETLAND RESERVE I000	MOULTRIE COUNTY CONSTRUCTION CODE: WEST OKAW FISH AND WILDLIFE UNIT I000	MOULTRIE COUNTY CONSTRUCTION CODE: KASKASKIA FISH AND WILDLIFE UNIT I000
20200100	EARTH EXCAVATION	CU YD	1937	10	442	1485
20400800	FURNISHED EXCAVATION	CU YD	775	0	650	125
21400100	GRADING AND SHAPING DITCHES	FOOT	1070	75	410	585
25000200	SEEDING, CLASS 2	ACRE	8	0.25	3.50	4.25
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	720	22	315	383
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	720	22	315	383
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	720	22	315	383
25100115	MULCH, METHOD 2	ACRE	8	0.25	3.50	4.25
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	800	25	350	425
28000300	TEMPORARY DITCH CHECKS	EACH	241	2	29	210
28000400	PERIMETER EROSION BARRIER	FOOT	5679	10	2912	2757
28100105	STONE RIPRAP, CLASS A3	SQ YD	6			6
28200100	FILTER FABRIC	SQ YD	6			6
35800100	PREPARATION OF BASE	SQ YD	11747		2786	8961
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	15277	320	6314	8643
40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	3288		762	2526
40300300	BITUMINOUS MATERIALS (COVER AND SEAL COATS)	GALLON	8906		2430	6476
40300500	COVER COAT AGGREGATE	TON	152		39	113
40300600	SEAL COAT AGGREGATE	TON	119		34	85
50105220	PIPE CULVERT REMOVAL	FOOT	1372		424	948
542D0217	PIPE CULVERTS, CLASS D, TYPE 1, 12"	FOOT	945		465	480
542D0220	PIPE CULVERTS, CLASS D, TYPE 1, 15"	FOOT	268	48	176	44
542D0223	PIPE CULVERTS, CLASS D, TYPE 1, 18"	FOOT	456			456
542D0229	PIPE CULVERTS, CLASS D, TYPE 1, 24"	FOOT	42		42	
542D0253	PIPE CULVERTS, CLASS D, TYPE 1, 48"	FOOT	36			36
542D1093	PIPE CULVERTS, CLASS D, TYPE 2, 48"	FOOT	40			40
60900515	CONCRETE THRUST BLOCKS	EACH	2		2	
* 53000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	54		27	27
* 63200305	STEEL PLATE BEAM GUARD RAIL REMOVAL	FOOT	49		25	24
67100100	MOBILIZATION	L SUM	1	0.34	0.33	0.33
70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	L SUM	1		0.5	0.5
X0300019	REMOVE AND REINSTALL PARKING BLOCKS	EACH	8		6	2
X0301797	GATE REMOVAL	EACH	58		31	27
X0325520	FURNISHING AND INSTALLING STEEL GATE ASSEMBLY 24'	EACH	17		3	14
X0325521	FURNISHING AND INSTALLING STEEL GATE ASSEMBLY 30'	EACH	43		29	14
X0325522	REINSTALLING EXISTING STEEL GATE ASSEMBLY	EACH	1		1	
Z0068900	STONE LINED DITCH	TON	827		497	330

*SPECIALTY ITEMS

CODED NO	DESCRIPTION	UNIT	QUANTITY	CONSTRUCTION CODE: MARGARET GUZY POTHOLE WETLAND RESERVE I000-2A	CONSTRUCTION CODE: WEST OKAW FISH AND WILDLIFE UNIT I000-2A	CONSTRUCTION CODE: KASKASKIA FISH AND WILDLIFE UNIT I000-2A

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES FOR SHELBYVILLE STATE FISH & WILDLIFE AREAS

SCALE: DRAWN BY BANDY
DATE CHECKED BY STEUART