

| | | | | |
|-------------------------|----------|------------------|--------------|-----------|
| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 116 | * | RICHLAND | 43 | 4 |
| STA. | TO STA. | | | |
| FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT | | |
| * (123Z, 124Z)TS-2,RS-3 | | | | |

SUMMARY OF QUANTITIES

HSIP

| CODE NO | ITEM | UNIT | URBAN TOTAL QUANTITIES | CONSTRUCTION TYPE CODE | | | | |
|----------|---|-------|------------------------|------------------------------|----------------------------|---------------------------------|---|----------------------|
| | | | | 1000 F 80% FED./20% STATE | 1000 90% FED./10% STATE | Y031-IF 90%-FED 10%-STATE | Y031-IF 90%-FED 5%-STATE 5%-CITY | Y031-IF 100%-CITY |
| 70300240 | TEMPORARY PAVEMENT MARKING - LINE 6" | FOOT | 4501 | 4501 | | | | |
| 70300260 | TEMPORARY PAVEMENT MARKING - LINE 12" | FOOT | 143 | 143 | | | | |
| 70300280 | TEMPORARY PAVEMENT MARKING - LINE 24" | FOOT | 395 | 395 | | | | |
| 70301000 | WORK ZONE PAVEMENT MARKING REMOVAL | SQ FT | 4614 | 4614 | | | | |
| 72000200 | SIGN PANEL - TYPE 2 | SQ FT | 128 | | 40 | 88 | | |
| 78000100 | THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS | SQ FT | 920 | | 920 | | | |
| 78000200 | THERMOPLASTIC PAVEMENT MARKING - LINE 4" | FOOT | 12933 | | 12933 | | | |
| 78000400 | THERMOPLASTIC PAVEMENT MARKING - LINE 6" | FOOT | 4226 | | 4226 | | | |
| 78000600 | THERMOPLASTIC PAVEMENT MARKING - LINE 12" | FOOT | 143 | | 143 | | | |
| 78000650 | THERMOPLASTIC PAVEMENT MARKING - LINE 24" | FOOT | 357 | | 357 | | | |
| 78005100 | EPOXY PAVEMENT MARKING - LETTERS AND SYMBOLS | SQ FT | 83 | | 83 | | | |
| 78005130 | EPOXY PAVEMENT MARKING - LINE 6" | FOOT | 275 | | 275 | | | |
| 78005180 | EPOXY PAVEMENT MARKING - LINE 24" | FOOT | 38 | | 38 | | | |
| 78100100 | RAISED REFLECTIVE PAVEMENT MARKER | EACH | 541 | | 541 | | | |
| 78300100 | PAVEMENT MARKING REMOVAL | SQ FT | 2269 | 2269 | | | | |
| 80500200 | SERVICE INSTALLATION, TYPE B | EACH | 2 | | | 1 | 1 | |
| 80802000 | WOOD POLE, 35 FT., CLASS 3 | EACH | 1 | | | 1 | | |
| 81012400 | CONDUIT IN TRENCH, 1 1/4" DIA., PVC | FOOT | 86 | | | | 86 | |
| 81012600 | CONDUIT IN TRENCH, 2" DIA., PVC | FOOT | 341 | | | 214 | 127 | |
| 81013000 | CONDUIT IN TRENCH, 4" DIA., PVC | FOOT | 109 | | | 109 | | |
| 81021590 | CONDUIT, AUGERED 4" DIA., PVC | FOOT | 254 | | | 254 | | |
| 81100600 | CONDUIT ATTACHED TO STRUCTURE, 2" DIA., GALVANIZED STEEL | FOOT | 20 | | | 20 | | |
| 81400100 | HANDHOLE | EACH | 5 | | | 5 | | |
| 81400300 | DOUBLE HANDHOLE | EACH | 1 | | | 1 | | |
| 81500200 | TRENCH AND BACKFILL FOR ELECTRICAL WORK | FOOT | 530 | | | 323 | 207 | |
| 81702450 | ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 10 | FOOT | 1146 | | | | | 1146 |
| 82103250 | LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, PHOTO-CELL CONTROL, 250 WATT | EACH | 5 | | | | | 5 |
| 84200500 | REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE | EACH | 2 | | | 2 | | |
| 84200700 | LIGHTING FOUNDATION REMOVAL | EACH | 2 | | | 2 | | |
| 85700200 | FULL-ACTUATED CONTROLLER AND TYPE IV CABINET | EACH | 1 | | | 1 | | |
| 87301225 | ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C | FOOT | 602 | | | | 602 | |
| 87301245 | ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C | FOOT | 3454 | | | 1165 | 2289 | |

*

* SPECIALTY ITEMS

| REVISIONS | |
|-----------|------|
| NAME | DATE |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. DATE
HORIZ. DATE

DRAWN BY
CHECKED BY

5/19/2006
c:\projects\74161\1d03406pa.dgn

PLOT DATE = 5/19/2006
PLOT SCALE = AS SHOWN
USER NAME = district