CONTRACT NO. 74188

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	*	FAYETTE	5	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* D7 BIT RESURF 2007-1

SUMMARY OF QUANTITIES

	SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
	CODE NO	ITEM	UNIT		1000 100% STATE		
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	459	459		
	44000007	BITUMINOUS SURFACE REMOVAL 2"	SQ YD	2801	2801		
	44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	1875	1875		
	67100100	MOBILIZATION	L SUM	1	1		
	~~70100330~~	~~TRAFFIC CONTROL AND PROTECTION, STANDARD 701426~~	~~L SUM~~	~~1~~	~~1~~		
	70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	1		
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	5278	5278		
*	78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	360	360		
*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	6	6		
	X4066530	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N105	TON	514	514		
	X4066660	POLYMERIZED BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N105	TON	289	289		

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

Rev

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. HORIZ.

DATE

DRAWN BY

CHECKED BY

PLOT DATE = 5/10/2006
FILE NAME = c:\pw_work\74188\d06l06sum32
PLOT SCALE = 180.2786 ' / IN.
USER NAME = hammerwjp