

# SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
600	34RS-2	MADISON	39	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SUMMARY OF QUANTITIES			100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		I000	-----	-----
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	8.9	8.9		
40600300	AGGREGATE (PRIME COAT)	TON	44	44		
40600895	CONSTRUCTING TEST STRIP	EACH	1	1		
40600990	TEMPORARY RAMP	SQ YD	347	347		
40800040	INCIDENTAL BITUMINOUS SURFACING	TON	189	189		
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	148	148		
42400800	DETECTABLE WARNINGS	SQ FT	18	18		
44000006	BITUMINOUS SURFACE REMOVAL 1 1/2"	SQ YD	28303	28303		
44000009	BITUMINOUS SURFACE REMOVAL 3"	SQ YD	996	996		
44000100	PAVEMENT REMOVAL	SQ YD	32	32		
44000300	CURB REMOVAL	FOOT	84	84		
44000600	SIDEWALK REMOVAL	SQ FT	148	148		
44200140	PAVEMENT PATCHING, TYPE I, 12 INCH	SQ YD	9	9		
44200144	PAVEMENT PATCHING, TYPE II, 12 INCH	SQ YD	397	397		
44200148	PAVEMENT PATCHING, TYPE III, 12 INCH	SQ YD	176	176		
44200150	PAVEMENT PATCHING, TYPE IV, 12 INCH	SQ YD	1028	1028		
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	1861	1861		
48202000	BITUMINOUS SHOULDERS SUPERPAVE	TON	77	77		
60406500	FRAMES AND LIDS, SPECIAL	EACH	4	4		
60600505	CONCRETE CURB (SPECIAL)	FOOT	48	48		
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	66	66		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6		
67100100	MOBILIZATION	L SUM	1	1		
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	1		
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1		
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	5189	5189		
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1122	1122		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	26591	26591		
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1149	1149		
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	174	174		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	10736	10736		
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1122	1122		

SUMMARY OF QUANTITIES			100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		I000	-----	-----
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	26591	26591		
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1149	1149		
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	174	174		
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	865	865		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	314	314		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	314	314		
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	2526	2526		
X4066428	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N90	TON	2195	2195		
Z0018200	DRAINAGE STRUCTURE RECONSTRUCTION (SPECIAL)	EACH	5	5		

4401714  
 5/17/2006  
 c:\projects\7100\plan\p1-089.dgn  
 \*REF\*  
 \*REF\*

\*SPECIALTY ITEMS

PLOT DATE: 5/17/2006