

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
600	34RS-2	MADISON	39	5
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____ ILLINOIS FED. AID PROJECT				

PATCHING SCHEDULE

LOCATION	LANE			LENGTH (FEET)	WIDTH (FEET)	TYPE 1 (SQ YDS)	TYPE 2 (SQ YDS)	TYPE 3 (SQ YDS)	TYPE 4 (SQ YDS)	COMMENTS
	NB	TL	SB							
993+20	X			20	12				26.67	
997+50	X			15	12				20.00	
998+10			X	4	12		5.33			
998+40			X	100	3				33.33	
999+00			X	20	7			15.55		
1000+40			X	6	12		8.00			
1000+40		X		6	12		8.00			
1004+25			X	20	12				26.67	
1004+35	X			10	12			13.33		
1006+20			X	6	12		8.00			
1006+85	X			12	12			16.00		
1007+75	X			4	12		5.33			
1007+75		X		4	12		5.33			
1007+75			X	4	12		5.33			
1009+20	X			6	12		8.00			
1009+20			X	4	12		5.33			
1009+90			X	30	12				40.00	
1010+85			X	4	12		5.33			
1011+20	X			4	12		5.33			
1011+55	X			4	12		5.33			
1011+55		X		4	12		5.33			
1012+66	X			4	12		5.33			
1012+66		X		4	12		5.33			
1012+66			X	4	12		6.22			
1013+10	X			4	6	2.67				
1015+50	X			4	12		5.33			
1017+05	X			6	6	4.00				
1018+10	X			4	12		5.33			
1018+10		X		4	12		5.33			
1019+50			X	25	6			16.67		
1020+50	X			4	12		5.33			
1020+50		X		4	12		5.33			
1020+50			X	4	12		5.33			
1021+15	X			4	12		5.33			
1023+35	X			6	12		8.00			
1023+35		X		6	12		8.00			
1023+35			X	6	12		8.00			
1025+00	X			14	15			18.67		
78+10			X	32	6				21.33	
78+29			X	4	14		6.22			
78+79			X	4	14		6.22			
78+29		X		4	14		6.22			
79+84			X	6	14		8.00			
79+84	X			80	8				71.11	
80+29	X			4	14		6.22			

LOCATION	LANE			LENGTH (FEET)	WIDTH (FEET)	TYPE 1 (SQ YDS)	TYPE 2 (SQ YDS)	TYPE 3 (SQ YDS)	TYPE 4 (SQ YDS)	COMMENTS
	NB	TL	SB							
80+29		X		4	12		5.33			
80+29			X	4	14		6.22			
81+52			X	4	14		6.22			
82+03				25	6			16.67		
82+51			X	4	14		6.22			
82+51		X		4	12		5.33			
82+78			X	16	14				24.89	
83+26	X			8	14		12.44			
83+47			X	20	14				31.11	
83+75	X			4	14		6.22			
83+75		X		4	12		5.33			
83+75			X	4	14		6.22			
84+93			X	18	6		12.00			
85+16	X			16	6		10.67			
85+77			X	4	14		6.22			
86+28			X	4	6		2.67			
86+43			X	4	14		6.22			
86+76		X		4	12		5.33			
86+76			X	4	14		6.22			
87+28			X	6	12		9.33			
87+74	X			4	14		6.22			
87+74		X		4	12		5.33			
87+74			X	4	14		6.22			
88+80			X	6	14		9.33			
89+00	X			55	14				85.56	
90+00	X			10	14			15.67		
90+00			X	10	14			15.67		
91+26	X			10	14			15.67		
91+26		X		10	12		13.33			
91+26			X	10	14			15.67		
92+00			X	166	14				258.22	
92+42	X			26	6					
94+21			X	4	4	1.77				
94+38			X	20	14				31.11	
95+50	X			90	14				140.00	
96+09	X			4	14		6.22			
96+09		X		4	12		5.33			
98+06			X	80	14				124.44	
SUB-TOTALS						8.44	361.21	159.57	934.44	
10% FOR ANTICIPATED FAILURES						0.84	36.12	15.96	93.44	
TOTALS						9	397	176	1028	

DRAINAGE STRUCTURES

LOCATION	DRAINAGE STRUCTURE RECONSTRUCTION (SPECIAL)	FRAMES AND LIDS (SPECIAL)	CONCRETE CURB (SPECIAL)	COMMENTS
STATION	EACH	EACH	FOOT	
1004+57	1			South East Corner
1011+77	1			904 Troy Road
1015+60	1	1	12	822-824 Troy Road
1021+65		1	12	743 Troy Road
1023+32		1	12	Near Water Tower
84+66	1			401 South Buchanon
86+48	1	1	12	326 South Buchanon
Total	5	4	48	

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

PATCHING & DRAINAGE STRUCTURE SCHEDULES

FAP ROUTE 600
SECTION 34RS-2
MADISON COUNTY

PLAN
NO. _____
DATE _____
BY _____
CHECKED _____
DATE _____
FILE NAME _____

4/25/06
5/15/2006
c:\p\proj\34rs-2\100\plan\p1n095a.dgn
REF
REF