

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
785	132-3I-1	MADISON	14	4
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

EARTHWORK SCHEDULE		
LOCATION STATION	CHANNEL EXCAVATION CU YD	EMBANKMENT CU YD
STA. 10+78.65 TO STA. 10+80	3.50	0.70
STA. 10+80 TO STA. 10+90	35.80	16.10
STA. 10+90 TO STA. 11+00	11.00	28.80
STA. 11+00 TO STA. 11+10	7.30	50.50
STA. 11+10 TO STA. 11+12.02	2.10	14.60
STA. 11+12.02 TO STA. 11+20	14.60	83.10
STA. 11+20 TO STA. 11+30	38.90	128.20
STA. 11+30 TO STA. 11+40	60.80	96.50
STA. 11+40 TO STA. 11+50	69.00	60.40
STA. 11+50 TO STA. 11+60	80.40	40.60
STA. 11+60 TO STA. 11+70	88.00	37.00
STA. 11+70 TO STA. 11+80	72.50	46.50
STA. 11+80 TO STA. 11+90	55.00	37.60
STA. 11+90 TO STA. 12+00	40.70	27.30
STA. 12+00 TO STA. 12+10	32.00	18.00
STA. 12+10 TO STA. 12+20	30.80	10.00
STA. 12+20 TO STA. 12+30	25.40	14.30
STA. 12+30 TO STA. 12+40	19.50	15.10
STA. 12+40 TO STA. 12+40.69	0.70	0.30
TOTAL	688.00	725.60
FURNISH EXCAVATION 38 CU YD		

PLOT DATE = 5/18/2006
 FILE NAME = I:\Projects\76988\132-3I-1\132-3I-1.dgn
 PLOT SCALE = 50,0000' / IN.
 REFERENCE = #REF#

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION <i>SCHEDULES</i>
NAME	DATE	
		FAP 785 SECTION 132-3I-1 MADISON COUNTY SCALE: VERT. DRAWN BY DATE HORIZ. CHECKED BY

Rev.