

SUMMARY OF QUANTITIES

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1398	06-00241-00-TL	COOK	23	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		


83860 83860

LOCATION OF WORK				FAU ROUTE 1398 (CHICAGO AVENUE)				
SUMMARY OF QUANTITIES				CONSTRUCTION CODE	Y031-1F	Y031-1F	Y031-1F	Y031-1F
SP	CODE NO.	ITEM	UNIT	TOTAL	SEA of MARION ST.	KENILWORTH AVE.	OAK PARK AVE.	INTERCONNECT
	67100100	MOBILIZATION	L. SUM	1				1
*	70102625	TRAFFIC CONTROL AND PROTECTION STANDARD 701606	L. SUM	1	0.3	0.3	0.3	0.1
*	70102630	TRAFFIC CONTROL AND PROTECTION STANDARD 701601	L. SUM	1	0.3	0.3	0.3	0.1
*	70102635	TRAFFIC CONTROL AND PROTECTION STANDARD 701701	L. SUM	1	0.3	0.3	0.3	0.1
*	70102640	TRAFFIC CONTROL AND PROTECTION STANDARD 701801	L. SUM	1	0.3	0.3	0.3	0.1
	81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FT	3,044	523	495	501	1525
	81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FT	60	60			
	81400100	HANDHOLE	EACH	7	2	2	2	1
	85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	3	1	1	1	
	85700500	FULL-ACTUATED CONTROLLER IN EXISTING CABINET	EACH	1		1		
	86400100	TRANSCEIVER - FIBER OPTIC	EACH	2				2
	87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FT	2,129	688	684	757	
	87900200	DRILL EXISTING HANDHOLE	EACH	10	4	3	3	
	88500100	INDUCTIVE LOOP DETECTOR	EACH	6	2	2	2	
	88600100	DETECTOR LOOP, TYPE I	FT	217	74	71	72	
	88800100	PEDESTRIAN PUSH-BUTTON	EACH	1		1		
	89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1		1		
	X0322925	ELECTRIC CABLE IN CONDUIT, TRACER, NO 14/1C	FOOT	2,364				2364
*	XX002056	REOPTIMIZE EXISTING SIGNAL SYSTEM	EACH	1				1
	XX003660	FIBER OPTIC CABLE IN CONDUIT NO. 62.5/125 MM24F SM 12F	FT	2,364				2364
	XX00666A	MODIFY EXISTING CABINET EQUIPMENT AND APPURTENANCES	EACH	4				4

TIME: 6:23:48 PM

DATE: 5/30/2006

FILENAME: s:\06\751-800\784\084\inters\sh\schedule\summary-quantities.dgn

	REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
	NAME	DATE	
SCALE: VERT. NONE		DRAWN BY RCB	
HORIZ. DATE 5/30/2006			
		CHECKED BY KCV	