

SUMMARY OF QUANTITIES

F.A.U. ROUTE	CONTRACT NO.	COUNTY	TOTAL SHEETS
5348	87330	DEKALB	140
STATE SECTION			6
05-00160-00-WR			
SUMMARY OF QUANTITIES			
F.H.W.A. REG.5		ILLINOIS PROJECT	HPP-2295(001)

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE								
				1000-2A ROADWAY	X028-2A BOX CULVERT	Y003 LANDSCAPING ORNAMENTAL	Y030-1E LIGHTING	Y030-1F SIGNALS S. MALTA RD./TAYLOR ST.	Y031-1F SIGNALS INTERCONNECT	Y080 TRAINING	Y060 NON-PART.	
* 81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	127						127			
* 81001100	CONDUIT IN TRENCH, 5" DIA., GALVANIZED STEEL	FOOT	16						16			
* 81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	1,323						213	1,110		
* 81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	790				400		390			
* 81019000	CONDUIT PUSHED, 5" DIA., GALVANIZED STEEL	FOOT	90				90					
* 81400100	HANDHOLE	EACH	18						4	14		
* 81400200	HEAVY-DUTY HANDHOLE	EACH	3						3			
* 81400300	DOUBLE HANDHOLE	EACH	2						2			
* 81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	5,729				2,589		850	2,290		
* 81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/2 NO. 10	FOOT	12,608				10,710		1,896			
* 82103400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, PHOTO-CELL CONTROL, 400 WATT	EACH	4						4			
* 82500505	LIGHTING CONTROLLER, SPECIAL	EACH	1				1					
* 83600300	LIGHT POLE FOUNDATION, 30" DIAMETER	FOOT	192				192					
* 83600315	LIGHT POLE FOUNDATION, 30" DIAMETER, OFFSET	FOOT	36				36					
* 84200500	REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE	EACH	1				1					
* 84200700	LIGHTING FOUNDATION REMOVAL	EACH	1				1					
* 84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	1				1					
* 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	2							2		
* 85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1						1			
* 85900100	TRANSCIVER	EACH	1						1			
* 87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	1,517						1,517			
* 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	1,930						1,930			
* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	2,020						2,020			
* 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	2,081						2,081			
* 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	2,366						2,366			
* 87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	113						113			
* 87301815	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 3 C	FOOT	120	120								
* 87502440	TRAFFIC SIGNAL POST, GALVANIZED STEEL 10 FT.	EACH	1						1			
* 87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	4						4			
* 87702940	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 42 FT.	EACH	1						1			
* 87702970	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 48 FT.	EACH	1						1			
* 87702985	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 52 FT.	EACH	1						1			
* 87703000	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 55 FT.	EACH	1						1			
* 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	20						20			
* 87800200	CONCRETE FOUNDATION, TYPE D	FOOT	4						4			
* 87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	60						60			
* 87900200	DRILL EXISTING HANDHOLE	EACH	1							1		
* 88200100	TRAFFIC SIGNAL BACKPLATE	EACH	11						11			
* 88500100	INDUCTIVE LOOP DETECTOR	EACH	11						11			
* 88800100	DETECTOR LOOP, TYPE I	FOOT	1,255						1,255			
* 88800100	PEDESTRIAN PUSH-BUTTON	EACH	8						8			
* 89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1						1			
* 89501400	RELOCATE EXISTING EMERGENCY VEHICLE PRIORITY SYSTEM, DETECTOR UNIT	EACH	2						2			
* 89501410	RELOCATE EXISTING EMERGENCY VEHICLE PRIORITY SYSTEM, PHASING UNIT	EACH	1						1			
* 89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1						1			
* 89502380	REMOVE EXISTING HANDHOLE	EACH	4						4			
* 89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	8						8			
* A2004724	TREE, GLEDITSIA TRIACANTHOS INERMIS SHADEMASTER (SHADEMASTER THORNLESS COMMON HONEYLOCUST), 3" CALIPER, BALLED AND BURLAPPED	EACH	30					30				
* A2008024	TREE, TILIA CORDATA (LITTLE LEAF LINDEN) 3" CALIPER, BALLED AND BURLAPPED	EACH	25					25				
* C2005824	SHRUB, RHUS AROMATICA GRO-LOW (GRO-LOW FRAGRANT SUMAC), 2" WIDTH, BALLED AND BURLAPPED	EACH	60					60				
* K1005481	SHREDDED BARK MULCH 3"	SQ YD	1,500					1,500				
X0321558	SANITARY MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	5	5								
X0322033	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	FOOT	20	20								
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	18	18								
X0322671	STABILIZED CONSTRUCTION ENTRANCE	SQ YD	730	730								
* X0323885	TRAFFIC SIGNAL BATTERY BACKUP SYSTEM	EACH	1						1			
X0712400	TEMPORARY PAVEMENT	SQ YD	2,365	2,365								

* SPECIALTY ITEM