

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
332	(29, 29X) RS-2	GALLATIN/SALINE	15	10
STA.		TO STA.		
FED. ROAD DIST. NO. _		ILLINOIS	FED. AID PROJECT	

CONTRACT NO. 98942

PAVEMENT MARKING SCHEDULE

LOCATION			LENGTH (FT)	THERMOPLASTIC PAVEMENT MARKING							SHORT TERM PAVEMENT MARKING (FT)	TEMP. PAVEMENT MARKING - LINE 4" (FT)	TEMP. PAVEMENT MARKING - LINE 12" (FT)	TEMP. PAVEMENT MARKING - LINE 24" (FT)	TEMP PAVEMENT MARKING - LETTERS & SYMBOLS (SQ FT)	WORK ZONE PAVEMENT MARKING REMOVAL (SQ FT)	RAISED REFLECTIVE PAVEMENT MARKERS (EACH)	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL (EACH)
				4" YELLOW SKIP DASH (FT)	4" SOLID YELLOW NO PASSING (FT)	4" SOLID WHITE LINE (FT)	12" SOLID YELLOW LINE (FT)	12" SOLID WHITE LINE (FT)	24" SOLID WHITE LINE (FT)	LETTERS & SYMBOLS (SQ FT)								
STATION	TO	STATION	(FT)	(FT)	(FT)	(FT)	(FT)	(FT)	(FT)	(FT)	(FT)	(FT)	(FT)	(SQ FT)	(SQ FT)	(EACH)	(EACH)	
SALINE COUNTY - URBAN SECTION																		
395+00	TO	402+55	755	378	1510					62	604	1888		62	692	38	38	
402+55	TO	405+22	267		846	341	60	28		36	191	1187	88	36	520	17	17	
405+22	TO	406+22	100						89	42				42	220			
406+22	TO	411+40	518		1840	1100	92	74		78	391	2940	166	78	1224	35	35	
411+40	TO	412+50	110		220	220					66	440			147	4	4	
412+50	TO	422+06	956	239		1912					287	2151			717	12	12	
422+06	TO	428+61	655	164	655	1310					197	2129			710	8	8	
428+61	TO	433+20	459		918	918					138	1836			612	6	6	
433+20	TO	444+45	1125	282	1125	2250					338	3657			1219	14	14	
444+45	TO	477+06	3261	815	6522						978	7337			2446	41	41	
477+06	=	459A+59																
459A+59	TO	469A+33	974	244	1948						292	2192			731	12	12	
469A+33	TO	471A+26	193	48	193	386					58	627			209	2	2	
SUBTOTAL - SALINE CO. URBAN				2169	7307	16907	152	102	89	218	3539	26384	254	89	218	9445	189	
SALINE COUNTY - RURAL SECTION																		
471A+26	TO	477A+00	574	144	574	1148					172	1866			622	7	7	
477A+00	=	477+00																
477+00	TO	481+89	489	122	978						147	1100			367	6	6	
481+89	TO	487+86	597	149	597	1194					179	1940			647	7	7	
487+86	TO	516+42	2856	714	5712						857	6426			2142	36	36	
516+42	TO	522+18	576	144	576	1152					173	1872			624	7	7	
522+18	TO	528+15	597	149	597	1194					179	1343			448	7	7	
528+15	TO	533+48	533	133	533	1066					160	1732			577	7	7	
533+48	TO	598+39	6491	1623	12982				16		1947	14605		16	4900	81	81	
598+39	TO	676+84																
676+84	TO	703+38	2654	664	5308				16		796	5972		16	2023	33	33	
703+38	TO	722+34	1896	474	3792						569	4266			1422	24	24	
722+34	TO	763+00	4066	1017	8132						1220	9149			3050	51	51	
SUBTOTAL - SALINE CO. RURAL				5332	2280	42658			32		6399	50270		32	16821	267	267	
GALLATIN COUNTY																		
763+00	TO	768+00	500	125	1000						150	1125			375	6	6	
768+00	TO	773+00	500	125	500	1000					150	1625			542	6	6	
773+00	TO	775+40	240		480	480					72	960			320	3	3	
775+40	TO	783+00	760	190	760	1520					228	2470			823	10	10	
783+00	TO	791+60	860	215	1720						258	1935			645	11	11	
791+60	TO	802+80	1120	280	1120	2240					336	3640			1213	14	14	
802+80	TO	819+80	1700		3400	3400					510	6800			2267	21	21	
819+80	TO	826+17	637	159	637	1274					191	2070			690	8	8	
SUBTOTAL - GALLATIN CO. RURAL				1094	6897	12634					1895	20625			6875	79	79	
TOTALS				8596	16484	72199	152	102	121	218	11833	97279	254	121	218	33141	535	535
				97279			254											

NOTE: 24" AIR SPEED MARKINGS ARE TO BE REPLACED AT THE FOLLOWING STATIONS:

- STA. 556+80
 - STA. 563+40
 - STA. 706+80
 - STA. 713+40
- (SEE GENERAL NOTE 7)

PLOT DATE = 5/18/2006
 FILE NAME = D:\Program Development\Studies and Plans\Upstairs Design\Projects\US 45 3P-Eldorado\Plans\plans.dgn
 PLOT SCALE = 1/8" = 100'
 USER NAME = thomashf