

PLOT DATE = 5/18/2006
 FILE NAME = G:\Program Development\Studies and Plans\Upstairs Design\Projects\US 45 3P-Eldorado\Plans\Plans.dgn
 PLOT SCALE = 108.4337' / IN.
 USER NAME = thomesht

PATCHING SCHEDULE

BASED ON PATCHING SURVEY PERFORMED ON 1/4/06 - FOR INFORMATIONAL PURPOSES ONLY

MILEAGE BEGINS AT INTERSECTION OF 4TH ST. & US 45 AND CONTINUES NORTHERLY	CLASS D PAVEMENT PATCHING							
	TYPE I	TYPE II	TYPE III	TYPE IV	TYPE I	TYPE II	TYPE III	TYPE IV
	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)
MI. TO MI.	SBL				NBL			
0.0 TO 0.2	7.8	49.5	27.4	0.0	10.4	54.3	25.4	0.0
0.2 TO 0.4	2.0	53.2	0.0	0.0	15.5	24.7	0.0	0.0
0.4 TO 0.6	5.9	36.7	0.0	0.0	0.0	45.8	0.0	0.0
0.6 TO 0.8	8.1	42.8	0.0	0.0	4.4	36.7	0.0	0.0
0.8 TO 1.0	0.0	29.0	0.0	0.0	13.4	0.0	0.0	0.0
1.0 TO 1.2	5.9	48.9	0.0	0.0	12.7	29.0	0.0	0.0
1.2 TO 1.4	3.9	15.3	0.0	0.0	18.0	50.4	0.0	0.0
1.4 TO 1.6	5.4	30.6	0.0	0.0	12.5	22.9	0.0	0.0
1.6 TO 1.8	5.9	35.1	0.0	0.0	2.9	36.7	0.0	0.0
1.8 TO 2.0	12.7	27.5	0.0	0.0	10.8	45.8	0.0	0.0
2.0 TO 2.2	4.4	51.9	0.0	0.0	12.7	32.1	0.0	0.0
2.2 TO 2.4	9.8	18.3	0.0	0.0	7.3	13.8	0.0	0.0
2.4 TO 2.6	5.9	15.3	0.0	0.0	4.9	19.9	0.0	0.0
2.6 TO 2.8	6.8	18.3	0.0	0.0	0.0	24.4	0.0	0.0
2.8 TO 3.0	9.7	30.3	0.0	0.0	2.4	32.1	0.0	0.0
3.0 TO 3.2	6.8	27.5	0.0	0.0	2.9	32.1	0.0	0.0
3.2 TO 3.4	21.5	36.7	0.0	0.0	5.9	41.3	0.0	0.0
3.4 TO 3.6	8.3	36.7	0.0	0.0	8.4	41.3	0.0	0.0
3.6 TO 3.8	3.9	55.0	0.0	0.0	5.4	48.9	0.0	0.0
3.8 TO 4.0	26.4	42.8	0.0	0.0	25.5	64.2	0.0	0.0
4.0 TO 4.2	5.4	21.4	0.0	0.0	6.8	21.4	0.0	0.0
4.2 TO 5.6	OMISSION							
5.6 TO 5.8	2.9	51.9	0.0	0.0	0.0	76.4	0.0	0.0
4.8 TO 6.0	2.0	26.0	0.0	0.0	2.0	39.7	0.0	0.0
5.0 TO 6.2	0.0	45.8	0.0	0.0	0.0	53.5	0.0	0.0
5.2 TO 6.4	5.4	38.2	0.0	0.0	0.0	68.8	0.0	0.0
5.4 TO 6.6	0.0	58.1	0.0	0.0	0.0	45.8	0.0	0.0
5.6 TO 6.8	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
5.8 TO 7.0	5.5	18.8	0.0	0.0	0.0	7.6	0.0	97.8
6.0 TO 7.2	4.9	59.6	0.0	0.0	22.4	32.1	0.0	0.0
6.2 TO 7.4	13.4	18.3	0.0	0.0	8.1	44.1	0.0	0.0
6.4 TO 7.6	5.6	80.7	0.0	30.6	4.9	74.9	0.0	0.0
6.6 TO 7.8	13.9	53.5	0.0	30.6	2.9	39.7	0.0	0.0
6.8 TO 8.0	0.0	38.2	0.0	0.0	0.0	36.7	0.0	0.0
7.0 TO 8.2	2.9	32.1	0.0	0.0	0.0	45.8	0.0	0.0
7.2 TO 8.4	2.9	21.4	0.0	0.0	0.0	6.1	0.0	0.0
TOTALS	225.8	1265.2	27.4	61.1	223.1	1288.8	25.4	97.8

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
332	(29, 29X) RS-2	GALLATIN/SALINE	15	11
STA.		TO STA.		
FED. ROAD DIST. NO. _		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 98942				

GUARDRAIL SCHEDULE

LOCATION STATION TO STATION	GUARDRAIL REMOVAL FOOT	SPBGR TYPE A FOOT	TRAFFIC BARRIER TERMINAL		GUARDRAIL MARKERS EACH	TERMINAL MARKERS DIRECT APPLIED EACH	REMARKS
			TYPE 1, SPECIAL (TAN)	TYPE 2			
			EACH	EACH			
SFTY-2A							
RT & LT 702+58 TO 702+83	50.0						REMOVE END SECTIONS
RT 701+33 TO 702+83		100.0	1		2	1	
LT 701+83 TO 702+83		50.0	1		1	1	
RT & LT 706+39 TO 706+64	50.0						REMOVE END SECTIONS
RT 706+39 TO 707+39		50.0	1		1	1	
LT 706+39 TO 707+89		100.0	1		2	1	
RT & LT 719+42.5 TO 719+67.5	50.0						REMOVE END SECTIONS
RT & LT 719+47.0 TO 719+67.5		50.0		2	1	1	EXTEND FROM EXISTING RAIL AT 30' RADIUS
RT & LT 722+78.5 TO 723+03.5	50.0						REMOVE END SECTIONS
RT & LT 722+78.5 TO 722+99.0		50.0		2	1	1	EXTEND FROM EXISTING RAIL AT 30' RADIUS
LT 745+20	25.0		1		1	1	TERMINAL UPDATE
LT 730+90	25.0		1		1	1	TERMINAL UPDATE
PROJECT TOTALS:	250	400	6	4	10	8	