



EARTHWORK SCHEDULE

LOCATION	EARTH EXCAVATION	CHANNEL EXCAVATION	ESTIMATED UNSUITABLE MATERIAL	SUITABLE MATERIAL ADJUSTED FOR SHRINKAGE	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
	CUBIC YARD	CUBIC YARD	CUBIC YARD	CUBIC YARD	CUBIC YARD	CUBIC YARD
STA. 0+00 TO 4+61.7	8.7	0.0	0.0	6.5	176.5	-170.0
STA. 4+61.7 TO 5+38.3	0.0	205.0	102.5	76.8	0.0	76.8
STA. 5+38.3 TO 10+00	9.5	0.0	0.0	7.1	241.6	-234.5
STA. 5+35 TO 6+60 CREEK SIDE SLOPES	53.4	0.0	0.0	40.0	0.0	40.0
TOTAL	71.6	205.0	102.5	130.4	418.1	-287.4

T.R.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
229	01-06128-00-BR	HAMILTON	14	3

323 W. 3RD ST.
P.O. BOX 160
MT. CARMEL, IL
62863
PHONE: (618)-262-8651
FAX: (618)-263-3327

405 W. STATE ST.
SUITE 1
PRINCETON, IN
47370
PHONE: (812)-386-7611
FAX: (812)-385-2812

PROFESSIONAL DESIGN FIRM
LAND SURVEY & PROFESSIONAL ENGINEERING CORPORATION
184-000887
(62-032435)(35-002769)

AARON M. MEFFORD
NAME
SIGNATURE
DATE
11-30-07
EXPIRES

TOWNSHIP ROUTE 229
OVER SULLIVAN BRANCH
HAMILTON COUNTY, ILLINOIS

SHEET TITLE:
CROSS-SECTIONS
SCALE: 1" = 5'
BY: AMM
DATE: 9/4/06
REV: MLG
3 OF 14 SHEETS
SHEET NO.
3