



EARTHWORK QUANTITIES											
LOCATION	THEORETICAL		THEORETICAL TOPSOIL SOURCES		TOPSOIL REQUIRED		ADJUSTED EARTH			BORROW EXCAVATION	REMARKS
	CUT	FILL	IN CUT	IN FILL	IN CUT	IN FILL	UNCLASSIFIED EXCAVATION (CUT)	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE	EMBANKMENT (FILL)		
	(C.Y.)	(C.Y.)	(C.Y.)	(C.Y.)	(C.Y.)	(C.Y.)	(C.Y.)	(C.Y.)	(C.Y.)		
	(A)	(B)	(C)	(D)	(E)	(F)	(A)+(E)	G(0.75)	(B)+(D)	(I) - (H)	
ENTIRE PROJECT	45285	44030	18039	4489	4987	4557	50272	37704	48519	10815	
TOTAL							50272	---	---	10815	
	PAY ITEM									PAY ITEM	