

SUMMARY OF QUANTITIES

ITEM NO.	DESCRIPTION	UNIT	TTY L EST. QUANTITY	NE QUAD EST. QUANTITY	TOTAL EST. QUANTITY	RECORD QUANTITY
AR108084	1/C #4 XLP-USE	L.F.	800	0	800	
AR108108	1/C #8 SKV UG CABLE	L.F.	7,395	655	8,050	
AR108758	1/C #8 GROUND	L.F.	400	0	400	
AR110202	2" PVC DUCT, DIRECT BURY	L.F.	5,490	600	6,090	
AR110212	2" STEEL DUCT, DIRECT BURY	L.F.	425	0	425	
AR110213	3" STEEL DUCT, DIRECT BURY	L.F.	0	180	180	
AR110214	4" STEEL DUCT, DIRECT BURY	L.F.	0	180	180	
AR110216	5" STEEL DUCT, DIRECT BURY	L.F.	0	180	180	
AR110502	2-WAY CONCRETE ENCASED DUCT	L.F.	420	0	420	
AR110504	4-WAY CONCRETE ENCASED DUCT	L.F.	0	55	55	
AR110550	SPLIT DUCT	L.F.	40	0	40	
AR110610	ELECTRICAL HANDHOLE	EACH	12	2	14	
AR110900	REMOVE DUCT	L.F.	50	0	50	
AR125100	ELEVATED RETROREFLECTIVE MARKER	EACH	0	19	19	
AR125415	MITL - BASE MOUNTED	EACH	60	0	60	
AR125442	TAXI GUIDANCE SIGN, 2 CHARACTER	EACH	5	0	5	
AR125443	TAXI GUIDANCE SIGN, 3 CHARACTER	EACH	1	2	3	
AR125444	TAXI GUIDANCE SIGN, 4 CHARACTER	EACH	1	1	2	
AR125445	TAXI GUIDANCE SIGN, 5 CHARACTER	EACH	3	0	3	
AR125446	TAXI GUIDANCE SIGN, 6 CHARACTER	EACH	3	0	3	
AR125449	TAXI GUIDANCE SIGN, 9 CHARACTER	EACH	1	0	1	
AR125525	HURL INPAVEMENT	EACH	1	0	1	
AR125565	SPLICE CAN	EACH	5	0	5	
AR125902	REMOVE BASE MOUNTED LIGHT	EACH	23	0	23	
AR125904	REMOVE TAXI GUIDANCE SIGN	EACH	5	0	5	
AR125915	RELOCATE RGL	PAIR	1	0	1	
AR150510	ENGINEER'S FIELD OFFICE	L.S.	1	0	1	
AR152410	UNCLASSIFIED EXCAVATION	C.Y.	16,605	15,530	32,135	
AR152540	SOIL STABILIZATION FABRIC	S.Y.	13,000	14,300	27,300	
AR156510	SILT FENCE	L.F.	3,555	2,055	5,610	
AR156511	DITCH CHECK	EACH	5	0	5	
AR156520	INLET PROTECTION	EACH	17	29	46	
AR201610	BITUMINOUS BASE COURSE	TON	535	1,630	2,165	
AR208515	POROUS GRANULAR EMBANKMENT	C.Y.	4,520	450	4,970	
AR209606	CRUSHED AGG. BASE COURSE - 6"	S.Y.	10,445	0	10,445	
AR209607	CRUSHED AGG. BASE COURSE - 7"	S.Y.	0	14,300	14,300	
AR209618	CRUSHED AGG. BASE COURSE - 18"	S.Y.	2,340	0	2,340	
AR401610	BITUMINOUS SURFACE COURSE	TON	865	1,630	2,495	
AR401650	BITUMINOUS PAVEMENT MILLING	S.Y.	3,000	0	3,000	
AR401900	REMOVE BITUMINOUS PAVEMENT	S.Y.	3,095	25	3,120	
AR501510	10" PCC PAVEMENT	S.Y.	10,220	0	10,220	
AR501530	PCC TEST BATCH	EACH	1	0	1	
AR501900	REMOVE PCC PAVEMENT	S.Y.	253	0	253	
AR602510	BITUMINOUS PRIME COAT	GAL.	585	3,575	4,160	
AR603510	BITUMINOUS TACK COAT	GAL.	705	1,430	2,135	
AR620520	PAVEMENT MARKING - WATERBORNE	S.F.	10,640	5,915	16,555	
AR620525	PAVEMENT MARKING - BLACK BORDER	S.F.	10,245	7,045	17,290	
AR620900	PAVEMENT MARKING REMOVAL	S.F.	1,300	1,545	2,845	
AR701415	15" RCP, CLASS III	L.F.	0	995	995	
AR701418	18" RCP, CLASS III	L.F.	210	0	210	
AR701430	30" RCP, CLASS III	L.F.	0	360	360	
AR701436	36" RCP, CLASS III	L.F.	0	215	215	
AR701442	42" RCP, CLASS III	L.F.	325	0	325	
AR701512	12" RCP, CLASS IV	L.F.	0	585	585	
AR701900	REMOVE PIPE	L.F.	360	440	800	
AR705526	6" PERFORATED UNDERDRAIN W/SOCK	L.F.	3,615	3,095	6,710	
AR705635	UNDERDRAIN COLLECTION STRUCTURE	EACH	0	1	1	
AR705900	REMOVE UNDERDRAIN	L.F.	845	0	845	
AR705905	REMOVE COLLECTION STRUCTURE	EACH	1	0	1	
AR751411	INLET - TYPE A	EACH	0	6	6	
AR751412	INLET - TYPE B	EACH	0	2	2	
AR751540	MANHOLE 4'	EACH	1	1	2	
AR751550	MANHOLE 5'	EACH	1	0	1	
AR751560	MANHOLE 6'	EACH	0	6	6	
AR751567	MANHOLE 7'	EACH	1	2	3	
AR751903	REMOVE MANHOLE	EACH	2	2	4	
AR751943	ADJUST MANHOLE	EACH	5	1	6	
AR751983	RECONSTRUCT MANHOLE	EACH	2	0	2	
AR760512	12" DUCTILE IRON WATER MAIN	L.F.	250	1,145	1,395	
AR760724	24" STEEL CASING	L.F.	70	0	70	
AR760800	FIRE HYDRANT	EACH	0	3	3	
AR760850	VALVE VAULT	EACH	0	2	2	
AR760862	12" X 12" TAPPING VALVE & SLEEVE	EACH	0	2	2	
AR760907	REMOVE WATER VALVE	EACH	1	0	1	
AR760945	ADJUST FIRE HYDRANT	EACH	0	1	1	
AR760965	RELOCATE FIRE HYDRANT	EACH	1	1	2	
AR800001	TYPE 1 INLET	EACH	0	12	12	
AR800028	SLOPE BOX INLET 18"	EACH	2	0	2	
AR800053	SOIL GUARD	S.Y.	4,725	6,195	10,920	
AR800194	REMOVE ELEVATED RETROREFLECTIVE MARKER	EACH	0	7	7	
AR800816	L-804 RGL ELEVATED, BASE MOUNTED	EACH	4	0	4	
AR901510	SEEDING	ACRE	5.7	2.7	8.4	
AR908510	MULCHING	ACRE	4.7	1.4	6.1	
LOCAL ONLY SHARE						
AR770512	12" SANITARY SEWER	L.F.	0	680	680	
AR770704	SANITARY MANHOLE 4'	EACH	0	2	2	

REVISIONS		
NUMBER	BY	DATE


0 1 2
 THIS BAR IS EQUAL TO 2"
 AT FULL SCALE (34X22).

**PALWAUKEE MUNICIPAL AIRPORT
 WHEELING/PROSPECT HEIGHTS, ILLINOIS**

SUMMARY OF QUANTITIES

© Copyright CMT, Inc.

CMT
 CRAWFORD, MURPHY & TILLY, INC.
 CONSULTING ENGINEERS
 License No. 984-00678



DESIGN BY:	MJS
DRAWN BY:	JRO
CHECKED BY:	
APPROVED BY:	
DATE:	06/29/06
JOB No:	06290-07
ILLINOIS PROJECT: PWK-3613 A.I.P. PROJECT: 3-17-0018-B39	
SHEET 2 OF 40 SHEETS	