

**908 MULCHING NOTES**

THE PROPOSED MULCHING SHALL BE ACCOMPLISHED IN ACCORDANCE WITH ITEM 908 "MULCHING" AS STATED ON PAGE 127 OF THE SUPPLEMENTAL SPECIFICATIONS AND RECURRING SPECIAL PROVISIONS, ADOPTED JULY 1, 2004.

THIS ITEM SHALL CONSIST OF THE FURNISHING, TRANSPORTING, AND PLACING MULCH OVER THE SEEDED AREA. DISTURBED AREAS OUTSIDE THE GRADING LIMITS SHALL ALSO BE MULCHED AND PARTICIPATION WILL BE THE SAME AS FOR SEEDED AREAS.

MULCH MATERIAL: THE CONTRACTOR WILL FURNISH HYDROMULCH AS THE TYPE OF MULCH MATERIAL TO BE USED ON THIS PROJECT, EXCLUSIVELY.

MULCHING: THE HYDRAULIC MULCH SHALL BE APPLIED AS A SLURRY OF 2,500 POUNDS OF MULCH AND NOT LESS THAN 2,500 GALLONS OF WATER PER ACRE.

STRUCTURE CLEANING: AFTER THE PROPOSED MULCH HAS BEEN APPLIED, THE CONTRACTOR WILL CLEAN THE MULCH OFF ALL STRUCTURES (DRAINAGE, ELECTRICAL, LIGHTS, ETC.).

DATE MULCHING COMPLETED \_\_\_\_\_

THE PROPOSED MULCHING WILL BE PAID FOR UNDER ITEMS:  
AR908510 MULCHING \_\_\_\_\_ 3.2 ACRES

**EROSION CONTROL BLANKET NOTES**

AN EROSION CONTROL MATERIAL (EXCELSIOR BLANKET) WILL BE INSTALLED AT THE LOCATIONS SHOWN ON SHEET NO. 4 AND IN ACCORDANCE WITH THE SPECIAL PROVISIONS.

**901 SEEDING NOTES**

THE PROPOSED SEEDING SHALL BE ACCOMPLISHED IN ACCORDANCE WITH ITEM 901 "SEEDING" AS STATED ON PAGE 120 OF THE SUPPLEMENTAL SPECIFICATIONS AND RECURRING SPECIAL PROVISIONS, ADOPTED JULY 1, 2004.

ALL DISTURBED AREAS LOCATED WITHIN THE PROPOSED GRADING AND SEEDING LIMITS WILL BE SEEDED IN ACCORDANCE WITH THE ABOVE NOTED SPECIFICATION. ALL AREAS OUTSIDE THE DESIGNATED GRADING AND SEEDING LIMITS WILL ALSO BE SEEDED BUT AT THE CONTRACTOR'S OWN EXPENSE.

ALL MATERIALS AND/OR DEBRIS RESULTING FROM THE SEEDING OPERATIONS WILL BE REMOVED FROM THE PAVEMENTS AND MISCELLANEOUS STRUCTURES PRIOR TO OPENING THE RUNWAY.


THE CONTRACTOR WILL BE REQUIRED TO ESTABLISH A GOOD STAND OF GRASS OF UNIFORM COLOR AND DENSITY TO THE SATISFACTION OF THE RESIDENT ENGINEER. IF AT THE TIME WHEN THE CONTRACT HAS BEEN OTHERWISE COMPLETED, IT IS NOT POSSIBLE TO MAKE AN ADEQUATE DETERMINATION OF COLOR, DENSITY, AND UNIFORMITY OF SUCH STAND OF GRASS, THE ITEM OF WORK WILL BE REVIEWED AT A LATER DATE DETERMINED BY THE ILLINOIS DIVISION OF AERONAUTICS.

DATE SEEDING COMPLETED \_\_\_\_\_

THE PROPOSED SEEDING WILL BE PAID FOR UNDER ITEMS:  
AR901510 SEEDING \_\_\_\_\_ 3.2 ACRES

**LEGEND**

- EXISTING PAVEMENT
- PROPOSED IMPROVEMENTS
- EXISTING GRADES
- PROPOSED GRADES
- PROPOSED GRADING AND SEEDING LIMITS
- EXISTING INLET
- EXISTING STORM SEWER
- PROPOSED INLET
- PROPOSED STORM SEWER



DATE	REVISION	BY

QUINCY REGIONAL AIRPORT  
BALDWIN FIELD  
ADAMS COUNTY, ILLINOIS

IL PROJ.: UN-3338  
A.I.P. PROJ.: 3-17-0085-XX

Project No. 82406TCD 0240	DATE 06/19/06
Revision R-191STK.DWG	DATE 06/19/06
Scale 1" = 50'	DATE 06/19/06
Drawn 06/19/06	DATE 06/19/06
Reviewed 07/12/06	DATE 07/12/06



REALIGN AND WIDEN TAXIWAY "C"  
PROPOSED STAKING PLAN

JUL 11, 2006 10:03 PM RAW I:\AIRPORTS\QUINCY\82406TCD\AIRPORT\SHEETS\R-191STK.DWG - STAKING