

REMOVE AND MODIFY EXISTING GUIDANCE SIGNS
SIZE 3, STYLE 2, CLASS 2

SIGN NUMBER	FACE	EXISTING LEGEND	LETTERS BACKGROUND	PROPOSED LEGEND ON REPLACEMENT PANELS	LETTERS BACKGROUND	CIRCUIT	PAY ITEMS	REMARK
5-5	NE		B B					
	SW	↖ C	B Y			SIGN	AR125904	REMOVE
9-7	W	← C	B Y					
	E		B B			SIGN	AR125904	REMOVE
13-7	NW	↙ C	B Y					
	SE		B B			SIGN	AR125904	REMOVE
23-5	NE	C ↘	B Y					
	SW		B B			SIGN	AR125904	REMOVE
27-6	W		B B					
	E	C →	B Y			SIGN	AR125904	REMOVE
31-5	NW		B B					
	SE	C ↗	B Y			SIGN	AR125904	REMOVE
B-1	NW		B B B B B B B B	23 -5 B2	W R W R Y B	T-F-2	AR125451 & AR125904	REMOVE EXISTING 4 MODULE SIGN & SUPPLY / INSTALL PROPOSED 3 MODULE SIGN WITH ALL NEW PANELS
	SE	B2 ← F →	B B Y B B Y B Y	B2 ← F →	Y B B Y B Y			
B-2 & B-3	NW	B2 23 -5	Y B W R W R			T-F-2	NONE	NO CHANGE
	SE	B2	Y B B B B B					
C-1	N		B B B B B B			T-F-2	AR125904	REMOVE
	S	← H ↖ F →	B Y B Y B Y					
C-2	N	↖ 31-13 ↘	W R W R W R B B			SIGN	AR125904	REMOVE
	S		B B B B B B B B					
C-3	N	← 2 7 - 9 →	W R W R W R			SIGN	AR125904	REMOVE
	S		B B B B B B					
C-4	N	↙ 2 3 - 5 ↗	W R W R W R			SIGN	AR125904	REMOVE
	S		B B B B B B					
C-5	N	C	Y B			SIGN	AR125904	REMOVE
	S		B B					
C-6	N		B B			SIGN	AR125904	REMOVE
	S	C	Y B					
C-7	N		B B			SIGN	AR125904	REMOVE
	S	C	Y B					
F-9	NW	F C → H ↘	Y B B Y B Y	F	Y B B B	T-F-2	AR125984 & AR801605	REFURBISH (EXISTING 3 MODULE SIGN TO PROPOSED 2 MODULE SIGN) & REPLACE 4 PANELS
	SE	F	Y B B B B B	F F ↑	Y B B Y			
F-10	NE	← C ↑ H F ↗	B Y B Y B Y	H ↑ F ↗	B Y B Y	T-F-2	AR125984 & AR801605	RELOCATE, REFURBISH (EXISTING 3 MODULE SIGN TO PROPOSED 2 MODULE SIGN) & REPLACE 4 PANELS
	SW	F	B B B B Y B	F ↑	B Y B B			
H-9	W	↙ F H F ↑ C →	B Y B B Y B Y	H F ↑	Y B B Y	T-F-2	AR125984 & AR801605	REFURBISH (EXISTING 4 MODULE SIGN TO PROPOSED 2 MODULE SIGN) & REPLACE 4 PANELS
	E		B B B B B B		B B B B			

LEGEND:

B/Y = BLACK LETTERS ON YELLOW BACKGROUND (TYPE L-858Y)
Y/B = YELLOW LETTERS ON BLACK BACKGROUND (TYPE L-858L)
B/B = BLACK BLANK PANEL
Y/Y = YELLOW BLANK PANEL
W/R = WHITE LETTERS ON RED BACKGROUND (TYPE L-858R)

N = NORTH NW = NORTHWEST
S = SOUTH SE = SOUTHWEST
E = EAST NE = NORTHEAST
W = WEST SW = SOUTHWEST

NUMBER OF MODULES	TRANSFORMER WATTAGE
1	100
2	300
3	500
4	500

* TRANSFORMERS SHALL BE 6.6/6.6 AMP.
* - OR AS REQUIRED BY SIGN MANUFACTURER.

NOTES:

1. THE AR125904 - REMOVE TAXI GUIDANCE SIGN CONTRACT UNIT PRICE SHALL INCLUDE THE REMOVAL / DISPOSAL OF THE SIGN, SIGN EQUIPMENT, P.C. CONCRETE SIGN BASE, AND SIGN TRANSFORMER BASE CAN. THIS ITEMS SHALL ALSO INCLUDE THE SUPPLYING / INSTALLING / COMPACTING OF SOIL BACKFILL, MULCHING & SEEDING AS REQUIRED. SEE THE SPECIAL PROVISIONS FOR ADDITIONAL INFORMATION.
2. THE AR125584 - REFURBISH TAXI GUIDANCE SIGN CONTRACT UNIT PRICE SHALL INCLUDE THE MODIFICATIONS TO THE SIGN AS DETAILED ABOVE, FULL DEPTH SAW CUTTING OF THE EXISTING SIGN BASE, REMOVAL / DISPOSAL OF THE ABANDON PORTION OF THE P.C. CONCRETE SIGN BASE, AND SUPPLYING / INSTALLING / COMPACTING OF SOIL BACKFILL, MULCHING & SEEDING AS REQUIRED. SEE THE SPECIAL PROVISIONS FOR ADDITIONAL INFORMATION.
3. THE AR125964 - RELOCATE TAXI GUIDANCE SIGN CONTRACT UNIT PRICE SHALL INCLUDE DISASSEMBLING SIGN EQUIPMENT, REMOVAL / DISPOSAL OF THE EXISTING P.C. CONCRETE SIGN BASE, SUPPLYING / INSTALLING / COMPACTING OF SOIL BACKFILL, MULCHING, SEEDING, EXCAVATION FOR NEW SIGN BASE, NEW P.C. CONCRETE SIGN BASE, AND REASSEMBLING SIGN EQUIPMENT. SEE SPECIAL PROVISIONS FOR ADDITIONAL INFORMATION.