

BY	
REVISION	
DATE	

SUMMARY OF QUANTITIES

ITEM NO.	DESCRIPTION	UNIT	AS AWARDED QUANTITIES	AS BUILT QUANTITIES
AR108158	1/C #8 5 KV UG CABLE IN UD	L.F.	288	
AR109210	VAULT MODIFICATIONS	L.S.	1	
AR110553	EXTEND 3-WAY DUCT	L.F.	50	
AR125961	RELOCATE STAKE MOUNTED LIGHT	EACH	61	
AR125962	RELOCATE BASE MOUNTED LIGHT	EACH	18	
AR125967	RELOCATE REILS	PAIR	2	
AR125970	RELOCATE PLAS	EACH	2	
AR150510	ENGINEER'S FIELD OFFICE	L.S.	1	
AR150540	HAUL ROUTE	L.S.	1	
AR152410	UNCLASSIFIED EXCAVATION	C.Y.	6,019	
AR152442	OFF-SITE BORROW EXCAVATION	C.Y.	3,342	
AR155540	BY-PRODUCT LIME	TON	617	
AR155616	SOIL PROCESSING - 16"	S.Y.	15,064	
AR156512	BALES	EACH	52	
AR156513	SEPARATION FABRIC	S.Y.	1,202	
AR156520	INLET PROTECTION	EACH	13	
AR156530	TEMPORARY SEEDING	ACRE	12	
AR201610	BITUMINOUS BASE COURSE	TON	7,497	
AR201630	BITUMINOUS BASE TEST SECTION	EACH	1	
AR209510	CRUSHED AGGREGATE BASE COURSE	TON	8,011	
AR401610	BITUMINOUS SURFACE COURSE	TON	1,602	
AR401900	REMOVE BITUMINOUS PAVEMENT	S.Y.	565	
AR602510	BITUMINOUS PRIME COAT	GAL.	5,430	
AR603510	BITUMINOUS TACK COAT	GAL.	6,675	
AR620520	PAVEMENT MARKING - WATERBORNE	S.F.	44,991	
AR620900	PAVEMENT MARKING REMOVAL	S.F.	14,938	
AR705410	POROUS BACKFILL	C.Y.	679	
AR705524	4" PERFORATED UNDERDRAIN W/SOCK	L.F.	8,685	
AR705630	UNDERDRAIN INSPECTION HOLE	EACH	23	
AR901510	SEEDING	ACRE	12	
AR908510	MULCHING	ACRE	12	

INDEX TO SHEETS

SHEET NO.	DESCRIPTION
1	COVER SHEET
2	SUMMARY OF QUANTITIES, INDEX TO SHEETS
3	PROPOSED SAFETY PLAN
4	PROPOSED CONSTRUCTION PLAN STA. 120+00 TO STA. 127+00
5	PROPOSED CONSTRUCTION PLAN STA. 127+00 TO STA. 143+00
6	PROPOSED CONSTRUCTION PLAN STA. 143+00 TO STA. 159+00
7	PROPOSED CONSTRUCTION PLAN STA. 159+00 TO STA. 171+09
8	PROPOSED STAKING PLAN STA. 120+00 TO STA. 127+00
9	PROPOSED STAKING PLAN STA. 127+00 TO STA. 143+00
10	PROPOSED STAKING PLAN STA. 143+00 TO STA. 159+00
11	PROPOSED STAKING PLAN STA. 159+00 TO STA. 171+09
12	PROPOSED DRAINAGE PLAN STA. 120+00 TO STA. 127+00
13	PROPOSED DRAINAGE PLAN STA. 127+00 TO STA. 143+00
14	PROPOSED DRAINAGE PLAN STA. 143+00 TO STA. 159+00
15	PROPOSED DRAINAGE PLAN STA. 159+00 TO STA. 171+09
16	EXISTING ELECTRICAL PLAN STA. 120+00 TO STA. 127+00
17	EXISTING ELECTRICAL PLAN STA. 127+00 TO STA. 135+00
18	EXISTING ELECTRICAL PLAN STA. 135+00 TO STA. 143+00
19	EXISTING ELECTRICAL PLAN STA. 143+00 TO STA. 159+00
20	EXISTING ELECTRICAL PLAN STA. 159+00 TO STA. 167+00
21	EXISTING ELECTRICAL PLAN STA. 167+00 TO STA. 171+09
22	PROPOSED ELECTRICAL PLAN STA. 120+00 TO STA. 127+00
23	PROPOSED ELECTRICAL PLAN STA. 127+00 TO STA. 135+00
24	PROPOSED ELECTRICAL PLAN STA. 135+00 TO STA. 143+00
25	PROPOSED ELECTRICAL PLAN STA. 143+00 TO STA. 159+00
26	PROPOSED ELECTRICAL PLAN STA. 159+00 TO STA. 167+00
27	PROPOSED ELECTRICAL PLAN STA. 167+00 TO STA. 171+09
28	ELECTRICAL DETAILS
29	ELECTRICAL DETAILS
30	ELECTRICAL NOTES
31	ELECTRICAL NOTES
32	PROPOSED P.L.A.S.I. DETAILS
33	EXISTING ELECTRICAL ONE LINE DIAGRAM FOR VAULT, PLAS'S & REIL'S
34	NEW ELECTRICAL ONE LINE DIAGRAM FOR VAULT, PLAS'S & REIL'S
35	PANEL BOARD SCHEDULES AND TRANSFORMER WIRING DIAGRAMS
36	PROPOSED MARKING PLAN STA. 120+00 TO STA. 127+00
37	PROPOSED MARKING PLAN STA. 127+00 TO STA. 143+00
38	PROPOSED MARKING PLAN STA. 143+00 TO STA. 159+00
39	PROPOSED MARKING PLAN STA. 159+00 TO STA. 171+09
40	PROPOSED STORM WATER POLLUTION PREVENTION PLAN STA. 120+00 TO STA. 146+00
41	PROPOSED STORM WATER POLLUTION PREVENTION PLAN STA. 146+00 TO STA. 171+09
42	PROPOSED CROSS-SECTIONS STA. 120+00 TO STA. 121+00
43	PROPOSED CROSS-SECTIONS STA. 121+50 TO STA. 122+50
44	PROPOSED CROSS-SECTIONS STA. 123+00 TO STA. 124+00
45	PROPOSED CROSS-SECTIONS STA. 124+50 TO STA. 125+50
46	PROPOSED CROSS-SECTIONS STA. 126+00 TO STA. 127+00
47	PROPOSED CROSS-SECTIONS STA. 127+50 TO STA. 128+50
48	PROPOSED CROSS-SECTIONS STA. 129+00 TO STA. 130+00
49	PROPOSED CROSS-SECTIONS STA. 130+50 TO STA. 131+50
50	PROPOSED CROSS-SECTIONS STA. 132+00 TO STA. 133+00
51	PROPOSED CROSS-SECTIONS STA. 133+50 TO STA. 134+50
52	PROPOSED CROSS-SECTIONS STA. 135+00 TO STA. 136+00
53	PROPOSED CROSS-SECTIONS STA. 136+50 TO STA. 137+50
54	PROPOSED CROSS-SECTIONS STA. 138+00 TO STA. 139+00
55	PROPOSED CROSS-SECTIONS STA. 139+50 TO STA. 140+50
56	PROPOSED CROSS-SECTIONS STA. 141+00 TO STA. 142+00
57	PROPOSED CROSS-SECTIONS STA. 142+50 TO STA. 143+50
58	PROPOSED CROSS-SECTIONS STA. 144+00 TO STA. 145+00
59	PROPOSED CROSS-SECTIONS STA. 145+50 TO STA. 146+50
60	PROPOSED CROSS-SECTIONS STA. 147+00 TO STA. 148+00
61	PROPOSED CROSS-SECTIONS STA. 148+50 TO STA. 149+50
62	PROPOSED CROSS-SECTIONS STA. 150+00 TO STA. 151+00
63	PROPOSED CROSS-SECTIONS STA. 151+50 TO STA. 152+50
64	PROPOSED CROSS-SECTIONS STA. 153+00 TO STA. 154+00
65	PROPOSED CROSS-SECTIONS STA. 154+50 TO STA. 155+50
66	PROPOSED CROSS-SECTIONS STA. 156+00 TO STA. 157+00
67	PROPOSED CROSS-SECTIONS STA. 157+50 TO STA. 159+00
68	PROPOSED CROSS-SECTIONS STA. 159+50 TO STA. 161+00
69	PROPOSED CROSS-SECTIONS STA. 161+50 TO STA. 162+50
70	PROPOSED CROSS-SECTIONS STA. 163+00 TO STA. 164+00
71	PROPOSED CROSS-SECTIONS STA. 164+50 TO STA. 165+50
72	PROPOSED CROSS-SECTIONS STA. 166+00 TO STA. 167+00
73	PROPOSED CROSS-SECTIONS STA. 167+50 TO STA. 168+50
74	PROPOSED CROSS-SECTIONS STA. 169+00 TO STA. 170+00
75	PROPOSED CROSS-SECTIONS STA. 170+50 TO STA. 171+50

ROBINSON MUNICIPAL AIRPORT
ROBINSON
CRAWFORD COUNTY, ILLINOIS

HEI Project No. 838-04RWY	File Name R-02ELP.DWG	Scale N/A	Date 02/25/04
LAYOUT	CCC	02/25/04	
DRAWN	CCC	02/25/04	
REVIEWED	CAH	03/05/04	



RUNWAY 9-27
WIDENING
SUMMARY OF QUANTITIES,
INDEX TO SHEETS