UNO45

K:\ChampaignAp\0605902\Draw\Sheets
FILE: 2 IDXSUM.dwg
UPDATE BY: Allan Draughon
PLOT DATE: 6/9/2006 8:43 AM

INDEX TO SHEETS

1	COVER SHEET
2	INDEX TO SHEETS & SUMMARY OF QUANTITIES
3	GENERAL NOTES
4	SITE PLAN
5	CONSTRUCTION ACTIVITY PLAN
6	EXISTING CONDITIONS
7	PROPOSED IMPROVEMENTS
8	TYPICAL SECTIONS
9	STAKING PLAN
10	PAVING & MISCELLANEOUS DETAILS
11	APRON LIGHT LAYOUT
12	APRON LIGHTING DETAILS
13	LIGHTING LEVELS
14	MARKING PLAN
15	MOORING EYE AND MISCELLANEOUS DETAILS
16	EROSION CONTROL DETAILS

SUMMARY OF QUANTITIES

ITEM NO.	ITEM DESCRIPTION	UNIT	QUANTITY
AR106502	APRON LIGHT POLE W/DOUBLE FIXTURE	EA	2
AR106905	REMOVE APRON LIGHT POLE AND FOUNDATION	EA	2
AR108608	3/C #8 600V UG CABLE	LF	450
AR108758	1/C #8 GROUND	LF	450
AR110501	1-WAY CONCRETE ENCASED DUCT	LF	125
AR150510	ENGINEER'S FIELD OFFICE	LS	1
AR152410	UNCLASSIFIED EXCAVATION	CY	250
AR156510	SILT FENCE	LF	100
AR201610	BITUMINOUS BASE COURSE	TON	400
AR209510	CRUSHED AGGREGATE BASE COURSE	TON	100
AR401610	BITUMINOUS SURFACE COURSE	TON	300
AR401665	BITUMINOUS PAVEMENT SAWING	LF	740
AR401900	REMOVE BITUMINOUS PAVEMENT	SY	2400
AR401910	REMOVE AND REPLACE BITUMINOUS PAVEMENT	SY	36
AR510510	TIE DOWN	EA	12
AR510515	GROUND ROD	EA	4
AR602510	BITUMINOUS PRIME COAT	GAL	700
AR603510	BITUMINOUS TACK COAT	GAL	400
AR620520	PAVEMENT MARKING-WATERBORNE	SF	60
AR800340	REMOVE FENCE POST FOUNDATION	LF	480
AR800341	REMOVE CURB ISLAND	SY	20

REVISIONS

NUMBER	BY	DATE

0 1 2
THIS BAR IS EQUAL TO 2" AT FULL SCALE (34x22).

WILLARD AIRPORT
UNIVERSITY OF ILLINOIS

REHABILITATE GA/SCHOOL APRON

INDEX TO SHEETS & SUMMARY OF QUANTITIES

© Copyright CMT, Inc.

CMT
CRAWFORD, MURPHY & TILLY, INC.
CONSULTING ENGINEERS
License No. 184-000613

DESIGN BY:	JEF
DRAWN BY:	CMT
CHECKED BY:	SMH
APPROVED BY:	JEF
DATE:	06/09/2006
JOB No:	0605902

IL. PROJECT NO. CMI-3589
AIP PROJ. NO. 3-17-00XX-XX

SHEET 2 OF 16 SHEETS