

# SUMMARY OF QUANTITIES - CONT

COUNTY:	FRANKLIN CO	FRANKLIN CO	FRANKLIN CO
ROUTE:	IL 149	IL 149	IL 149
FUNDING:	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE
LOCATION:	RURAL	STATE RURAL	RURAL
	ROADWAY	LIGHTING	BRIDGE
	0004	0021	0059

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	FRANKLIN CO ROADWAY 0004	FRANKLIN CO LIGHTING 0021	FRANKLIN CO BRIDGE 0059
72400310	REMOVE SIGN PANEL - TYPE 1	SQ FT	18	18		
72400330	REMOVE SIGN PANEL - TYPE 3	SQ FT	612	612		
* 72400710	RELOCATE SIGN PANEL - TYPE 1	SQ FT	10	10		
* 72400730	RELOCATE SIGN PANEL - TYPE 3	SQ FT	176	176		
72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	6,426	6,426		
* 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	483	483		
* 73000100	WOOD SIGN SUPPORT	FOOT	354	354		
* 73100100	BASE FOR TELESCOPING STEEL SIGN SUPPORT	EACH	29	29		
* 73400100	CONCRETE FOUNDATIONS	CU YD	16	16		
73700100	REMOVE GROUND MOUNTED SIGN SUPPORT	EACH	16	16		
73700200	REMOVE CONCRETE FOUNDATION - GROUND MOUNT	EACH	16	16		
* 78009000	MODIFIED URETHANE PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	883	883		
* 78009004	MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	FOOT	2,302	2,302		
* 78009008	MODIFIED URETHANE PAVEMENT MARKING - LINE 8"	FOOT	702	702		

△

\* SPECIALTY ITEM

△ REVISED 7-25-2023

REV. - MS

MODEL: S007 (Sheet) FILE NAME: P:\Road\p1\brdwy.com\2\DOT\Documents\DOT Office\District 8\CRD Project\7814\CD\Drawings\02\814-SQC-SQ2.dgn

USER NAME = Triston.Reid	DESIGNED -	REVISED -
PLOT SCALE = 0.16666633 / in.	DRAWN -	REVISED -
PLOT DATE = 5/23/2023	CHECKED -	REVISED -
	DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

SCALE: SHEET 11 OF 50 SHEETS STA TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
873	(28-5)K-1	FRANKLIN	162	11
CONTRACT NO. 78814				
ILLINOIS FED. AID PROJECT				