



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

July 28, 2023

SUBJECT: FAU 5834 & FAU 5834A (19th St. & 19th St. Alt.)
Section 19-00271-00-BT (Moline)
Rock Island County
Contract No. 85744
Item 063
August 4, 2023 Letting
Addendum (A)

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

- 1. Revised Plan Sheets 94, 105-110, & 112-114**
- 2. Revised page 33 of the Special Provisions**

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

4. Constructing new foundation in accordance with ~~details provided in the plans~~ *IDOT Highway Standard 836001 – Light Pole foundation. Anchor bolt number and locations shall match the existing light pole base.* All conduit and wiring inside the foundation and light pole shall be included in this pay item. Conduit and wiring between handholes and foundations will be paid for separately.
5. Re-erecting lighting unit on the new foundation.
6. All electrical work required to provide a functional lighting system.

Conduit and wiring will be paid for separately at the contract unit prices for those pay items.

The work described above shall be paid for at the contract unit price per each for REMOVE REERECT EXISTING LIGHT UNIT.

LIGHTING UNIT UPGRADE

This work shall be completed in accordance with Section 844 of the Standard Specifications. The work included in this item shall include the following:

1. Marking each ungrounded conductor clearly as a phase conductor.
2. Marking each neutral/white wire being used a line/phase conductor accordingly.
3. Installing a surge protect device on each pole.
4. Installing a fuse holder on each pole.
5. Providing five-amp fuse for each pole.

The work described above shall be paid for at the contract unit price per each for LIGHTING UNIT UPGRADE.

TREES, SHRUBS, PLANTING

This work shall be completed in accordance with Sections 253 and 254 of the Standard Specifications.

Quantities of each planting have been included in the plans for each planter bed. Exact locations for each planting will be determined by the Engineer.

This work shall be paid for at the contract unit price per each for the pay items specified in the plans.