

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
575	(8&14) R-3	WILL	390	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 60961				


SUMMARY OF QUANTITIES

LOCATION OF WORK: U.S. ROUTE 30 - STA. 716+77.10 TO STA. 846+13.54

PAY ITEM NO.	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	80% FEDERAL / 20% STATE		100% SUNNYLAND	80% FEDERAL / 20% STATE		100% MUNICIPALITY		80% FEDERAL / 20% STATE
				ROADWAY 1000-2A	ROCK RUN & SUNNYLAND DRAIN BOX CULVERTS Y007	RETAINING WALL Y007	SANITARY DIST. Y060	TRAFFIC SIGNALS Y031-1F	TRAINING Y060	CREST HILL	JOLIET
40600300	AGGREGATE (PRIME COAT)	TON	802	802							
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	100.0	100.0							
40600895	CONSTRUCTING TEST STRIP	EACH	2	2							
42101300	PROTECTIVE COAT	SQ YD	8476	8476							
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	46	46							
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	222	222							
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	1772	1772							
44000100	PAVEMENT REMOVAL	SQ YD	37918	37918							
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	9026	9026							
44000300	CURB REMOVAL	FOOT	1068	1068							
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	6164	6164							
44000600	SIDEWALK REMOVAL	SQ FT	1805	1805							
44002805	ISLAND REMOVAL	SQ FT	616	616							
44003100	MEDIAN REMOVAL	SQ FT	7757	7757							
44004250	PAVED SHOULDER REMOVAL	SQ YD	3594	3594							
44200274	PAVEMENT PATCHING, TYPE I	SQ YD	1926	1926							
44200276	PAVEMENT PATCHING, TYPE II	SQ YD	1605	1605							
44200278	PAVEMENT PATCHING, TYPE III	SQ YD	1284	1284							
44200280	PAVEMENT PATCHING, TYPE IV	SQ YD	963	963							
44213200	SAW CUTS	FOOT	4530	4530							
48101700	AGGREGATE SHOULDER (SPECIAL)	CU YD	1659.6	1659.6							
48202400	BITUMINOUS SHOULDERS SUPERPAVE 6"	SQ YD	543	543							
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1						
50104400	CONCRETE HEADWALL REMOVAL	EACH	3		3						
50104600	CONCRETE RETAINING WALL REMOVAL	FOOT	78	78							
50105220	PIPE CULVERT REMOVAL	FOOT	1404	1404							
50200100	STRUCTURE EXCAVATION	CU YD	411		411						
* 50200400	ROCK EXCAVATION FOR STRUCTURES	CU YD	5		5						
50300225	CONCRETE STRUCTURES	CU YD	203.9			203.9					
50300300	PROTECTIVE COAT	SQ YD	659			659					
50500505	STUD SHEAR CONNECTORS	EACH	2606.0			2606.0					
50800105	REINFORCEMENT BARS	POUND	67121		54691	12430					
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1160		120	1040					

L:\DOT\0006602\design\compas\Summaryof Quantities\SumQuan002.dgn

LEGEND:
 NON-PARTICIPATING WORK
 * SPECIALTY ITEM



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
 US ROUTE 30
 SHEET 2 OF 8

SCALE: N/A
 DATE: 3/1/05
 DRAWN BY: AMB
 CHECKED BY: KDF/AMB