

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
575	(B&I4) R-3	WILL	390	6
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
CONTRACT NO. 60961				

### SUMMARY OF QUANTITIES

LOCATION OF WORK: U.S. ROUTE 30 - STA. 716+77.10 TO STA. 846+13.54

PAY ITEM NO.	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	80% FED. / 20% STATE		100% FEDERAL / 20% STATE		<del>100% MUNICIPALITY</del>		80% FEDERAL / 20% STATE
				ROADWAY I000-2A	ROCK RUN & SUNNYLAND DRAIN BOX CULVERTS Y007	RETAINING WALL Y007	SUNNYLAND SANITARY DIST. Y060	TRAFFIC SIGNALS Y031-1F	<del>TRAINING Y000</del>	<del>CREST HILL</del>
50900805	PEDESTRIAN RAILING	FOOT	985.0		38.0	947.0				
51205200	TEMPORARY SHEET PILING	SQ FT	270.0		270.0					
51500100	NAME PLATES	EACH	1		1					
54002020	EXPANSION BOLTS 3/4 INCH	EACH	40		40					
54002050	EXPANSION BOLTS 3/4 INCH X 9 INCH	EACH	34		34					
54003000	CONCRETE BOX CULVERTS	CU YD	263.4		263.4					
54010802	PRECAST CONCRETE BOX CULVERT 8' X 2'	FOOT	560.0	560.0						
54011003	PRECAST CONCRETE BOX CULVERT 10' X 3'	FOOT	104.0	104.0						
54200637	PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 12"	FOOT	193.0	193.0						
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	4	4						
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	2	2						
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1	1						
54244405	FLUSH INLET BOX FOR MEDIAN, STANDARD 542546	EACH	1	1						
54247110	GRATING FOR CONCRETE FLARED END SECTION 18"	EACH	2	2						
54247130	GRATING FOR CONCRETE FLARED END SECTION 24"	EACH	1	1						
55019500	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 12"	FOOT	2640	2640						
55019600	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 15"	FOOT	410	410						
55019700	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 18"	FOOT	1474	1474						
55019800	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 21"	FOOT	451	451						
55019900	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 24"	FOOT	1042	1042						
55020100	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 30"	FOOT	354	354						
55020400	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 36"	FOOT	298	298						
55021600	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 12"	FOOT	3131	3131						
55021700	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 15"	FOOT	808	808						
55021800	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 18"	FOOT	1176	1176						
55021900	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 21"	FOOT	33	33						
55022000	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 24"	FOOT	1422	1422						
55022100	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 27"	FOOT	10	10						
55022200	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 30"	FOOT	30	30						
55022400	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 36"	FOOT	253	253						
55034300	STORM SEWERS, TYPE 1, REINFORCED CONCRETE ELLIPTICAL PIPE, SPAN 30, RISE 19	FOOT	283	283						
55039700	STORM SEWERS TO BE CLEANED	FOOT	9039	9039						
55100400	STORM SEWER REMOVAL 10"	FOOT	224	224						

L:\DOT\00066802\design\comps\SummaryofQuantities\SunQuan03.dgn

LEGEND:  
 NON-PARTICIPATING WORK



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SUMMARY OF QUANTITIES**  
 US ROUTE 30  
 SHEET 3 OF 8

SCALE: N/A  
 DATE: 3/1/05

DRAWN BY: AMB  
 CHECKED BY: KDF/AMB