

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
575	(B&I4) R-3	WILL	390	9
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 60961				

### SUMMARY OF QUANTITIES

LOCATION OF WORK: U.S. ROUTE 30 - STA. 716+77.10 TO STA. 846+13.54

PAY ITEM NO.	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	80% FEDERAL / 20% STATE		100%	80% FEDERAL / 20% STATE	100% MUNICIPALITY	80% FEDERAL / 20% STATE
				ROADWAY I000-2A	ROCK RUN & SUNNYLAND DRAIN BOX CULVERTS Y007	RETAINING WALL Y007	SUNNYLAND SANITARY DIST. Y060	TRAFFIC SIGNALS Y031-1F	<del>TRAINING Y000</del>
70300560	PAVEMENT MARKING TAPE, TYPE III, 12"	FOOT	2468.5	2468.5					
70300570	PAVEMENT MARKING TAPE, TYPE III, 24"	FOOT	815.3	815.3					
70300625	TEMPORARY PAINT PAVEMENT MARKING - LINE 4"	FOOT	84977.5	84977.5					
70300635	TEMPORARY PAINT PAVEMENT MARKING - LINE 6"	FOOT	100	100					
70300640	TEMPORARY PAINT PAVEMENT MARKING - LINE 8"	FOOT	3073.4	3073.4					
70300645	TEMPORARY PAINT PAVEMENT MARKING - LINE 12"	FOOT	3353.9	3353.9					
70300660	TEMPORARY PAINT PAVEMENT MARKING - LINE 24"	FOOT	359.5	359.5					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	27697	27697					
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1420	1420					
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	540	540					
* 72000100	SIGN PANEL - TYPE 1	SQ FT	78	78					
* 72900200	METAL POST - TYPE B	FOOT	208	208					
* 72400500	RELOCATE EXISTING SIGN PANEL ASSEMBLY - TYPE A	EACH	34	34					
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1674	1674					
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	34659	34659					
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	5670	5670					
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1185	1185					
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	1237	1237					
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1195	1195					
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	22	22					
* 78201000	TERMINAL MARKERS - DIRECT APPLIED	EACH	8	8					
78300100	PAVEMENT MARKING REMOVAL	SQ FT	9948	9948					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	206	206					
* 81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	335						335
* 83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	16						16
* 84200700	REMOVAL OF POLE FOUNDATION, (LIGHT)	EACH	2						2
* 84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	2						2
* 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	4						4
88600600	DETECTOR LOOP REPLACEMENT	FOOT	4608						4608
Z0001050	AGGREGATE SUBGRADE, 12"	SQ YD	70281	70281					
Z0002600	BAR SPLICERS	EACH	78			78			
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1					
<input type="checkbox"/> Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	114	114					

LEGEND:  
 NON-PARTICIPATING WORK  
 \* SPECIALTY ITEMS



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SUMMARY OF QUANTITIES**  
 US ROUTE 30  
 SHEET 6 OF 8  
 SCALE: N/A  
 DATE: 3/1/05  
 DRAWN BY: AMB  
 CHECKED BY: KDF/AMB

L:\DOT\0006602\design\compas\Summary of Quantities\SumQuan006.dgn